

CONSTR. CODE

90% FED
10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY
				0021 URBAN
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	88	88
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	1507	1507
* 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	140	140
* 78009000	MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31.2	31.2
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	12626	12626
* 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	88	88
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	92	92
78300100	PAVEMENT MARKING REMOVAL	SQ FT	5174	5174
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	92	92
* X0327693	HIGH FRICTION SURFACE TREATMENT	SQ YD	17390	17390
X7810400	TEMPORARY RAISED PAVEMENT MARKER	EACH	152	152
* X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	1507	1507
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	140	140
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	42	42



△ REVISED 4-4-16

* SPECIALTY ITEM

FILE NAME =	USER NAME = budzynskm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
\\ILR864EB\ID\INTEG\Illinois.gov\WJDDT\06	umensa\IDOT Offices\District 3\Projects\0266	DRAWN Date\03266F04-ahh-details.dgn	REVISED -					5605	(17 RS-4) I	BUREAU	5	4	
PLOT SCALE = 1/2" = 100'	CHECKED -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 66F04		
PLOT DATE = 2/1/2018	DATE -	REVISED -											