SUMMARY OF QUANTITIES

	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE 0021
	21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	51	51
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1	1
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1	1
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1
	25200100	SODDING	SQ YD	51	51
	25200200	SUPPLEMENTAL WATERING	UNIT	3	3
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	124	124
*	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1	1
	42001300	PROTECTIVE COAT	SQ YD	125	125
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1112	1112
	42400800	DETECTABLE WARNINGS	SQ FT	132	132
	44000600	SIDEWALK REMOVAL	SQ FT	932	932
	67100100	MOBILIZATION	L SUM	1	1
* #	66900200	NON-SPECIAL WASTE DISPOSAL	CUYD	29	29
* #	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1
* #	66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1
#	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1
#	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
#	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
*	72000100	SIGN PANEL - TYPE 1	SQ FT	409	409
*	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	9	9
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	240	240
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	366	366

* INDICATES SPECIALTY ITEM
\# INDICATES SPECIAL PROVISION

SUMMARY OF QUANTITIES

	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL	CONSTRUCTION TYPE CODE 0021
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	366	366
#	Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	118	118
#	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	182	182
#	Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	2	2
* #	X0325714	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	EACH	6	6
△ * #	XX008728	SOLAR POWERED LED FLASHING WARNING SIGN	EACH	7	7

* INDICATES SPECIALTY ITEM
\# INDICATES SPECIAL PROVISION

•FAU 407
FAU 424
FAP 332
FAU 423

COPYRIGHT © 2017 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. - 184-001121 - EXPIRES 4/30/2017
7/41/F 2/3/2016 9:34:53 AM
...\plotdrv\pdf-BW.Default.pt
...\CADD\Plots\50194_Ph2-PEN.tbl
I:\Chicago\SELCH\50194-SHTS\CADD\50194SHT-S00.dgn

BAXTER & WOODMAN Consulting Engineers

DESIGNED - LJF	REVISED - △ 4/8/16	
DRAWN - KAR	REVISED -	
CHECKED - TMS	REVISED -	
DATE - 11-20-15	FILE - 150194SHT-S00.dgn	

VILLAGE OF BEECHER
SAFE ROUTES TO SCHOOL

SUMMARY OF QUANTITIES

SCALE: NONE | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	14-00018-00-SG	WILL	14	3
		CONTRACT NO. 61C56		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT STRS-4009(348)		