

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
778	(2-B)-1	SALINE	74	5
FED. ROAD DIST. NO. 9 ILLINOIS FED. AID PROJECT				

PAVEMENT SCHEDULE									
LOCATION			35300410	35600500	40200800	40600100	420001200	48202800	X4066418
			PORTLAND CEMENT CONCRETE BASE COURSE, 9 1/2"	BITUMINOUS CONCRETE BASE COURSE WIDENING, 10"	AGGREGATE SURFACE COURSE, TYPE B	BITUMINOUS MATERIALS (PR CT)	PAVEMENT FABRIC	BITUMINOUS SHOULDERS SUPERPAVE, 10"	BIT CONC SURFACE CSE SUPERPAVE MIX "C", N90
STATION	TO	STATION	(SQ YD)	(SQ YD)	(TON)	(GALLON)	(SQ YD)	(SQ YD)	(TON)
STAGE I									
435+20	RT	436+08	69			6	69		6
434+77.5	LT	436+48.5		44					
434+13	RT	434+57			25				
432+96	RT	438+00				228		669	
STAGE II									
435+20	LT	436+08	166			15	166		14
433+34	LT	439+00				147		407	
MISC.					5				
TOTAL			235	44	30	396	235	1076	20

PREPARED BY: KMN - CHECKED BY:

DRAINAGE STRUCTURE SCHEDULE			
LOCATION			54200661
			PIPE CULVERTS TYPE I, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE, 36" (FOOT)
STATION	TO	STATION	
STAGE I			
434+09	RT	434+16	7
434+47	RT	434+69	22
TOTAL			29

PREPARED BY: KMN - CHECKED BY:

RIPRAP SCHEDULE				
LOCATION			28100109	28200100
			STONE RIPRAP CLASS 5A	FILTER FABRIC FOR USE WITH RIPRAP
STATION	TO	STATION	(SQ YD)	(SQ YD)
STAGE I				
435+29.9	RT	435+96.1	187	187
STAGE II				
435+29.9	LT	435+96.1	222	222
TOTAL			409	409

PREPARED BY: KMN - CHECKED BY:

EARTHWORK SCHEDULE (CU YD)			
		IL RTE 34	TOTAL
EARTH EXCAVATION	20200100	305	305
CHANNEL EXCAVATION (SUITABLE)	20300100	100	100
CHANNEL EXCAVATION (UNSUITABLE)	20300100	40	40
STRUCTURE EXCAVATION (SUITABLE)	(NOT A PAY ITEM)	1160	1160
STRUCTURE EXCAVATION (UNSUITABLE)	(NOT A PAY ITEM)	135	135
TOTAL SUITABLE EARTH, CHANNEL & STRUCTURE EXCAVATION	(NOT A PAY ITEM)	1565	1565
TOTAL SUITABLE EXCAVATION ADJUSTED FOR 25% SHRINKAGE	(NOT A PAY ITEM)	1175	1175
EMBANKMENT	(NOT A PAY ITEM)	460	460
NET FILL (LESS SUITABLE EXCAVATION ADJUSTED)	(NOT A PAY ITEM)	0	0
REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	20201200	0	0
FURNISHED EXCAVATION	20400800	0	0
POROUS GRANULAR EMBANKMENT, CA-10	20700200	105	105
POROUS GRANULAR EMBANKMENT, CA-7 OR CA-11	20700200	750	750

NOTE: ITEMS SHOWN AS 'NOT A PAY ITEM' ARE FOR INFORMATION ONLY

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION FAP ROUTE 778 (IL 34) SECS. (2-B)-1, SALINE COUNTY
NAME	DATE	
		<p>SCHEDULE OF QUANTITIES</p> <p>SCALE: VERT. DATE: HORIZ. DATE: DRAWN BY: CHECKED BY:</p>