

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
322	4-I	JACKSON	26	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 98807				

SHEET 1 OF 2

STP-RURAL 80% FEDERAL / 20% STATE JACKSON COUNTY				
CODE NUMBER	ITEM DESCRIPTION CONSTRUCTION TYPE CODE	UNIT	TOTAL QUANTITY	ROADWAY I000-1A
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	772	772
X4066528	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N90	TON	541	541
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	35	35
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	249	249
20200100	EARTH EXCAVATION	CU YD	3276	3276
25000115	SEEDING CLASS 1B	ACRE	1.4	1.4
25000350	SEEDING, CLASS 7	ACRE	1.4	1.4
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	224	224
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	168	168
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	168	168
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.8	2.8
25100115	MULCH, METHOD 2	ACRE	2.8	2.8
25100630	EROSION CONTROL BLANKET	SQ YD	6406	6406
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	280	280
28000300	TEMPORARY DITCH CHECKS	EACH	10	10
28000400	PERIMETER EROSION BARRIER	FOOT	225	225
28000500	INLET AND PIPE PROTECTION	EACH	2	2
28100205	STONE, RIPRAP CL A3	TON	78	78
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	510	510
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	37	37
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	634	634
40600300	AGGREGATE (PRIME COAT)	TON	10	10
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	1	1
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	170	170
40600990	TEMPORARY RAMP	SQ YD	88	88
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	21	21
42001300	PROTECTIVE COAT	SQ YD	80	80
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	40	40
44000002	BITUMINOUS SURFACE REMOVAL 1/2"	SQ YD	4780	4780
44000100	PAVEMENT REMOVAL	SQ YD	158	158
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	45	45
44000400	GUTTER REMOVAL	FOOT	765	765
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	9	9
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	36	36
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1389	1389
48100100	AGGREGATE SHOULDERS, TYPE A	TON	263	263
48202600	BITUMINOUS SHOULDERS SUPERPAVE, 8"	SQ YD	770	770
50105220	PIPE CULVERT REMOVAL	FOOT	30	30