

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

Various Routes  
D 4 OVD SIN STR REPL 2010-31  
Various Counties  
Sheet 3 of 30  
Contract Number 46095

District 4  
Schedule of Overhead Sign Structure Replacement

Location No.:	4-01	State I.D. No.:	4S090I074R099.6				
County:	Tazewell	Route:	I-74	M.P.:	99.6	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	78.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	524.00					
REMOVE OVERHEAD SIGN STRUCTURE-WALKWAY	FOOT	42.00					
SIGN PANEL OVERLAY	SQ FT	504.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	1.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.50					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	4.00					

Location No.:	4-02	State I.D. No.:	4S090U150L001.5				
County:	Tazewell	Route:	US-150	M.P.:	1.5	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A	FOOT	68.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	399.00					
REMOVE & REINSTALL WALKWAY	FOOT	41.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	11.00					
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	20.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00					

Location No.:	4-03	State I.D. No.:	4S090U024L001.3				
County:	Tazewell	Route:	US-24	M.P.:	1.3	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A	FOOT	71.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	495.50					
REMOVE & REINSTALL WALKWAY	FOOT	45.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	3.00					
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	20.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	4.00					

Location No.:	4-04	State I.D. No.:	4S090S116L006.3				
County:	Tazewell	Route:	IL-116	M.P.:	6.3	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	75.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	594.25					
REMOVE & REINSTALL WALKWAY	FOOT	47.00					
DISCONNECT / RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	21.50					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	3.00					

Location No.:	4-05	State I.D. No.:	4C048U074L048.0				
County:	Knox	Route:	I-74	M.P.:	48.0	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A	FOOT	30.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	144.00					
REMOVE OVERHEAD SIGN STRUCTURE-WALKWAY	FOOT	21.50					
REMOVE ELECTRIC SERVICE	EACH	1.00					
SIGN PANEL OVERLAY	SQ FT	144.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	7.12					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	1.00					

Location No.:	4-06	State I.D. No.:	4C048U034R007.9				
County:	Knox	Route:	US-34	M.P.:	7.9	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE-CANTILEVER, TYPE II-C-A	FOOT	30.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	176.00					
REMOVE OVERHEAD SIGN STRUCTURE-WALKWAY	FOOT	23.50					
REMOVE ELECTRIC SERVICE	EACH	1.00					
SIGN PANEL OVERLAY	SQ FT	176.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	8.73					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	1.00					

Location No.:	4-07	State I.D. No.:	4S072I474R004.9				
County:	Peoria	Route:	I-474	M.P.:	4.96	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I-A	FOOT	50.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	191.50					
REMOVE OVERHEAD SIGN STRUCTURE-WALKWAY	FOOT	34.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00					
REMOVE ELECTRIC SERVICE	EACH	1.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	20.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					