

REMOVAL SCHEDULE

PAY CODE #	20100110	44000200	44000300	44000500	44000600	44003100	
LOCATION	TREE REMOV 6-15	DRIVE PAVEMENT REM	CURB REM	COMB CURB GUTTER REM	SIDEWALK REMOVAL	MEDIAN REMOVAL	
ROAD	STATION	UNIT	SQ YD	FOOT	FOOT	SQ FT	SQ FT
U. S. ROUTE 30 (LINCOLN HWY.)	132+00 - 147+00		657	231			
	147+00 - 162+00		202	58	511	1224	192
	179+50 - 194+50	8	319	67			
	SUBTOTAL	8.0	1178.0	356.0	511.0	1224.0	192.0
MARLEY RD	MARLEY RD. (S) MARLEY RD. (N)				73		156
	SUBTOTAL	0.0	0.0	0.0	73.0	0.0	156.0
TOTAL		8	1178	356	584	1224	348

ROADWAY SCHEDULE

PAY CODE #	35501316	40600100	40603310	42300200	42400610	42400800	44200124	48101500	60600605	60603800	66600105	X0712400	X4021000	X4022000	X4024000		
LOCATION	HMA BASE CSE 8	BIT MATLS PR CT	HMA SC "C" N50	PCC DRIVEWAY PAVT 6	TEMP SIDEWALK	DETECTABLE WARNINGS	PAVT PATCH T3 10	AGGREGATE SHLDS B 6	CONC CURB TB	COMB CC&G TB6.12	FUR ERECT ROW MARKERS	TEMP PAVEMENT	TEMP ACCESS - PRIV ENT	TEMP ACCESS - COM ENT	TEMP ACCESS - FLD ENT	LIMESTONE SCREEN, 2	
ROAD	STATION	SQ YD	GALLON	TON	SQ YD	SQ FT	SQ FT	SQ YD	SQ YD	FOOT	FOOT	EACH	SQ YD	EACH	EACH	EACH	SQ YD
U. S. ROUTE 30 (LINCOLN HWY.)	132+00 - 147+00		87					482				2	582	1			
	147+00 - 162+00	71	150	8	102	1203	56	211	44	606	3	998	1		1		29
	179+50 - 194+50		84					41	536	57		559		1			
	SUBTOTAL	71	321	8	102	1203	56	41	1229	44	663	5	2139	1	2	1	29
MARLEY RD	MARLEY RD. (S) MARLEY RD. (N)		10									67					
	SUBTOTAL	0	10	0	0	0	0	0	0	0	2	67	0	0	0	0	0
TOTAL		71	331	8	102	1203	56	41	1229	44	663	7	2206	1	2	1	29

EROSION & LANDSCAPING SCHEDULE

PAY CODE #	21101615	25000210	25000400	25000500	25000600	25100630	28000400			
LOCATION	TOPSOIL F & P 4	SEEDING CL 2A	NITROGEN FERT NUTR	PHOSPHORUS FERT NUTR	POTASSIUM FERT NUTR	EROSION CONTR BLANKET	PERIMETER EROS BAR	TEMPORARY DITCH CHECKS	ABOVE GRADE INLET FILTERS	
ROAD	STATION	SQ YD	ACRE	POUND	POUND	POUND	SQ YD	FOOT	FOOT	EACH
U. S. ROUTE 30 (LINCOLN HWY.)	132+00 - 147+00	987	0.2	18	18	18	987	902		
	147+00 - 162+00	683	0.14	13	13	13	683	413		5
	179+50 - 194+50	3164	0.65	59	59	59	3164	544	151	3
	SUBTOTAL	4834	1	90	90	90	4834	1859	151	8
MARLEY RD	MARLEY RD. (S) MARLEY RD. (N)									
	SUBTOTAL	0	0	0	0	0	0	0	0	0
TOTAL		4834	1	90	90	90	4834	1859	151	8

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -		353	13-1	WILL	67	6			
		CHECKED -	REVISED -		SCALE: NTS SHEET NO. 1 OF 3 SHEETS STA. TO STA.			CONTRACT NO. 60152				
		PLOT DATE =	REVISED -		ILLINOIS FED. AID PROJECT							