

NOTES:

- 1. USE BLACK LETTERING ON ORANGE BACKGROUND.
- 2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
- 3. ERECT SIGN (1) WITH INSTALLED PANEL (2) ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
- 4. REMOVE PANEL 2 SOON AFTER THE START OF CONSTRUCTION.
- 5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
- 6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
- 7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

FILE NAME =	USER NAME = gaglianobt	DESIGNED -	REVISED	- R. MIRS 09-15-97
W:\diststd\22x34\tc22.dgn		DRAWN ~	REVISED	- R. MIRS 12-11-97
	PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED	-T. RAMMACHER 02-02-99
	PLOT DATE = 1/4/2008	DATE -	REVISED	- C. JUCIUS 01-31-07

STATE	: OF	ILLINOIS
DEPARTMENT	OF	TRANSPORTATION

ARTERIAL ROAD				F.A.P. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.				
INFORMATION SIGN					330	(464Y & 465Y) RS-3	соок	44	41			
						TC-22	CONTRACT	NO.	60166			
CALE: NONE	SHEET	NO. 1	OF 1	SHEE	TS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				