

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000 QUANTITY
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	43	43
40600300	AGGREGATE (PRIME COAT)	TON	211	211
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	160	160
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4350	4350
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	794	794
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	400	400
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	10,520	10,520
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2300	2300
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	15570	15570
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	27380	27380
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	62928	62928
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	60	60
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	1785	1785
44213200	SAW CUTS	FOOT	9632	9632
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	50	50
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	1067	1067
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	212	212
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	339	339
45100200	CRACK FILLING	POUND	3564	3564
55039700	STORM SEWERS TO BE CLEANED	FOOT	456	456
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	5	5
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	5	5
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	6	6
60404950	FRAMES AND GRATES, TYPE 24	EACH	5	5
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	5	5
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1

* SPECIALTY ITEM

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	100% STATE	1000 QUANTITY
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9985	9985
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	583	583
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	67782	67782
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2230	2230
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	9316	9316
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	8976	8976
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	372	372
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1110	1110
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	291	291
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33891	33891
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1115	1115
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	4648	4648
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	4488	4488
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	186	186
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	863	863
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	151	151
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	863	863
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	789	789
* X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52
* X8950200	REBUILD EXISTING HANDHOLE	EACH	2	2
* X8950210	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	2	2
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	98	98
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	1	1

FILE NAME = P:\2009\ME\09006_Var\Var-Ph11\CADD\W08_IL835\Shs\03-D168J21-sh1-IL835-500.dgn
 USER NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
 630.785.8110 voice, 630.839.2566 fax
 www.mps-il.com

MILLENNIA PROFESSIONAL SERVICES

DESIGNED - CJD
 DRAWN - CJD
 CHECKED - RPD
 DATE - 2/23/2010

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 83 (SOUTH)
 ILLINOIS RTE 56 TO WASHINGTON ST

SUMMARY OF QUANTITIES

F.A.P. RTE. 344	SECTION 543 R-1-RS	COUNTY DUPAGE	TOTAL SHEETS 27	SHEET NO. 3
CONTRACT NO. 60J21			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT	

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

P:\2009\ME\09006_Var\Var-Ph11\CADD\W08_IL835\Shs\03-D168J21-sh1-IL835-500.dgn