

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	DESCRIPTION	UNIT	50% STATE / 50% CITY			
			URBAN TOTAL QUANTITY	1000-2A STATE	KENILWORTH Y025	WINNETKA Y025
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	83	83	0	0
25200110	SODDING, SALT TOLERANT	SQ YD	83	83	0	0
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	71.2	68	0.2	3
40600300	AGGREGATE (PRIME COAT)	TON	353	339	1	13
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	132.3	127	0.3	5
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3,709	3,562	9	138
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	0	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	804	804	0	0
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1,909	1,909	0	0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7,419	7,124	19	276
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	750	750	0	0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	83,416	79,904	225	3,287
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	4,908	4,908	0	0
44000600	SIDEWALK REMOVAL	SQ FT	750	750	0	0
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,000	1,000	0	0
44002213	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/4"	SQ YD	10,488	10,488	0	0
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	2,500	2,500	0	0
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	3,500	3,500	0	0
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	1,600	1,600	0	0
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	1,600	1,600	0	0
<del>60300305</del>	<del>FRAMES AND LIDS TO BE ADJUSTED</del>	<del>EACH</del>	<del>75</del>	<del>75</del>	0	0
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	110	110	0	0
67000400	ENGINEERS FIELD OFFICE TYPE A	CAL MO	6	6	0	0
67100100	MOBILIZATION	L SUM	1	1	0	0
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	0	0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	0	0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,981	6,818	35	1,128
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	924	924	0	0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	79,812	68,184	346	11,282
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	12,090	12,090	0	0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,140	1,140	0	0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	2,540	2,540	0	0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	551	551	0	0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	39,815	34,001	173	5,641
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6,100	6,100	0	0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	570	570	0	0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1,270	1,270	0	0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,173	1,173	0	0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,173	1,173	0	0
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3,184	3,184	0	0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	0	0
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	411	411	0	0

60300310 FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) EACH 220 220  
 60406000 FRAMES AND LIDS, TYPE 1, OPEN LID EACH 10 10  
 70102622 TRAFFIC CONTROL AND PROTECTION, STANDARD 701602 L SUM 1 1  
 Z0018500 DRAINAGE STRUCTURES TO BE CLEANED EACH 40 40

H:\Jobs\2009\2009-120-RS-23\CAD\15-14.dgn

FILE NAME =	USER NAME = _USER_	DESIGNED - EF	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GREEN BAY ROAD/GLENCOE ROAD - SCOTT AVENUE TO 16TH STREET</b>		F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	PLOT SCALE = 50,0000' / IN.	DRAWN - EF	REVISED -		<b>SUMMARY OF QUANTITIES</b>		2744	2009-120 RS	COOK	29	3	
	PLOT DATE = 2/9/2010	CHECKED - RS	REVISED -		SCALE: NTS	SHEET NO.	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 60J73	
		DATE - 01-29-2010	REVISED -		(ILLINOIS) FED. AID PROJECT							

Rev.