

STATE STANDARDS

SHEET NO. TITLE

1	TITLE SHEET
2	GENERAL NOTES, STATE STANDARDS AND INDEX OF SHEETS
3-4	SUMMARY OF QUANTITIES
5	TYPICAL SECTIONS
6	STAGING TYPICAL SECTIONS
7	CONSTRUCTION STAGING PLAN - STAGE 1
8	CONSTRUCTION STAGING PLAN - STAGE 2
9	ROADWAY RESURFACING AND APPROACH OVERLAY PLAN
10	PAVEMENT MARKING PLAN
11-26	STRUCTURAL PLANS
27	BUTT JOINT AND HMA TAPER DETAILS
28	RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
29	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
30	TRAFFIC CONTROL FOR SHOULDER CLOSURE AND PARTIAL RAMP CLOSURE
31	ARTERIAL ROAD INFORMATION SIGN
	HIGHWAY STANDARDS

SHEET NO. TITLE

000001-05	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT REBARS
701411-06	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS ≥ 45 MPH
701501-05	URBAN LANE CLOSURE, 2L, 2W, UNDIVIDED
701602-04	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
701901-01	TRAFFIC CONTROL DEVICES
704001-06	TEMPORARY CONCRETE BARRIER

GENERAL NOTES

ALL ELEVATIONS ARE BASED ON UNITED STATES COAST AND GEODETIC SURVEY DATUM.

DIMENSIONS ARE IN ENGLISH UNITS UNLESS OTHERWISE NOTED.

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES (48 HOURS NOTIFICATION IS REQUIRED).

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.

ANY REFERENCE TO STANDARDS IN THE PLANS OR SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT LISTED IN THE PLANS WITH THE LATEST NUMBERS.

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING PROPERTIES.

THE RESIDENT ENGINEER SHALL CONTACT ~~MS. DEBBIE HANLON~~ **MR. DON CHIARUGI**, AREA TRAFFIC ENGINEER, AT ~~(847) 438-2300~~ **(847) 741-9857** AT A MINIMUM OF 2 WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKING.

THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

ALL WORK IS TO BE COMPLETED BY THE COMPLETION DATE. THE COMPLETION DATE FOR THIS CONTRACT IS SEPTEMBER 24, 2010

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORDED FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE DIRECTED BY THE ENGINEER.

DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - MJY, DC	REVISED -
DATE - 01/29/2010	REVISED -

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2678	163 HB-I-1	DUPAGE	31	2
D-91-275-10			CONTRACT NO. 60J85	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		