

URBAN

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	1000						CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10															
40600300	AGGREGATE (PRIME COAT)	TON	48	48															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	36	36															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	709	709															
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2647	2647															
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	23630	23630															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9939	9939															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3313	3313															
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	100	100															
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	52388	52388															
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1000	1000															
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200															
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200															
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	647	647															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	647	647															
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	200	200															
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	309	309															

* SPECIALTY ITEM

FILE NAME =	USER NAME = wlgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\work\PWIDOT\WILGREENDP\0183637\02signdp	DRAWN -	REVISED -	VAR.			2010-009 RS	MCHENRY	23	3	
PLOT SCALE = 1000000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 60K28							
PLOT DATE = 2/11/2010	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		