ROUTE: IL 47 (Ware Rd. to IL 173)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
Ware Rd.	Price Rd.	EB/WB	1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	3	100	300	33
			1	3	200	600	67
			1	3	50	150	17
			1	3	100	300	33
			1	3	50	150	17
			1	20	13	260	29
			1	6	25	150	17
			1	3	30	90	10
			1	3	100	300	33
			1	3	100	300	33
			1	13	30	390	43
			1	13	30	390	43
Ware Rd.	Price Rd.	EB/WB	1	20	13	260	29
			1	3	30	90	10
			1	3	30	90	10
			1	3	30	90	10
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	3	100	300	33
			1	4	100	400	44
			1	4	150	600	67
			1	4	100	400	44
			1	3	30	90	10
			1	6	50	300	33
			1	10	13	130	14
			1	4	50	200	22
			1	4	30	120	13
Ware Rd.	Price Rd.	EB/WB	1	6	50	300	33
		TOTALS:			8388 FT		3963 SY

FILE NAME = c:\pw_work\PWIDOT\WILGREENDP\d0183637\Design.dgn

USER NAME = wilgreendp
PLOT SCALE = 100.0000 ' / IN.
PLOT DATE = 2/13/2010

DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 47

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-009 RS	MCHENRY	23	7

CONTRACT NO. 60K28

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 2/13/2010 2:50:07 PM User=wilgreendp