ROUTE: IL 173 (US 14 to Boone County Line)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
US 14		EB/WB	1	26	40	1040	116
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	30	180	20
			1	3	30	90	10
			1	3	300	900	100
			1	6	25	150	17
			1	6	50	300	33
			1	3	100	300	33
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	3	100	300	33
			1	6	50	300	33
			1	6	13	78	9
			1	6	250	1500	167
			1	6	100	600	67
	White Oaks		1	6	30	180	20
White Oaks		EB/WB	1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	13	75	975	108
			1	6	13	78	9
			1	25	13	325	36
			1	6	12	72	8
			1	3	200	600	67
			1	3	150	450	50
			1	3	100	300	33
			1	13	25	325	36
			1	13	50	650	72
			1	13	30	390	43
			1	6	13	78	9
			1	6	13	78	9
			1	3	100	300	33
			1	3	30	90	10
			1	6	13	78	9
			1	3	30	90	10
			1	3	100	300	33

ROUTE: IL 173 (US 14 to Boone County Line)

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
			1	13	100	1300	144
			1	13	50	650	72
			1	3	50	150	17
			1	26	100	2600	289
			1	13	100	1300	144
			1	6	13	78	9
			1	13	100	1300	144
			1	13	100	1300	144
			1	13	100	1300	144
			1	3	200	600	67
			1	13	30	390	43
			1	3	250	750	83
			1	3	50	150	17
			1	3	100	300	33
			1	6	50	300	33
			1	13	30	390	43
			1	13	20	260	29
			1	13	20	260	29
			1	26	20	520	58
			1	6	25	150	17
			1	6	25	150	17
			1	3	250	750	83
			1	3	50	150	17
			1	3	1100	3300	367
			1	10	13	130	14
			1	6	13	78	9
			1	13	75	975	108
			1	13	50	650	72
			1	3	250	750	83
	Boone County Line		1	26	6	156	17
		TOTALS:			**5620**		**3712**
					FT		**SY**

FILE NAME = c:\pw_work\PWIDOT\WILGREENDP\d0183637\Design.dgn	USER NAME = wilgreendp	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 2/13/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 173

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-009 RS	MCHENRY	23	15

CONTRACT NO. 60K28

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

Design.dgn 2/13/2010 2:50:56 PM User=wilgreendp