ROUTE: IL 173 (Lake County Line to Fox River Bridge)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB)	NO.	PATCH	PATCH	AREA	AREA
		(NB/SB)	(1, 2, 3)	WIDTH	LENGTH	(SQ FT)	(SQ YD)
Lake County Line		EB/WB	1	3	100	300	33
			1	3	100	300	33
			1	3	30	90	10
			1	3	100	300	33
			1	13	20	260	29
			1	3	50	150	17
			1	3	100	300	33
			1	3	100	300	33
			1	10	13	130	14
			1	6	30	180	20
			1	3	100	300	33
			1	3	100	300	33
			1	3	100	300	33
			1	3	100	300	33
			1	3	50	150	17
			1	10	13	130	14
			1	10	13	130	14
			1	10	13	130	14
			1	10	13	130	14
			1	10	13	130	14
			1	3	100	300	33
			1	3	30	90	10
			1	6	100	600	67
			1	10	13	130	14
			1	10	13	130	14
			1	6	100	600	67
			1	13	100	1300	144
			1	13	100	1300	144
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
			1	6	13	78	9
	Fox River		1	6	13	78	9
		TOTALS:			**2117**		**1242**
					FT		**SY**

FILE NAME =	USER NAME = wilgreendp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PATCHING SCHEDULE IL 173	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
c:\pw_work\PWIDOT\WILGREENDP\d0183637\Design.dgn		DRAWN -	REVISED -			VAR.	2010-009 RS	MCHENRY	23 / 16
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -					CONTRACT NO. 60K28	
	PLOT DATE = 2/13/2010	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	