

ROUTE: Bluff Road Overpass (Between East and West Frontage Roads)							
CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
east frontage road	structure over I-55	WB	1	12	4	48	5
			1	12	4	48	5
structure over I-55	west frontage road	WB	1	12	4	48	5
			1	12	4	48	5
			1	12	4	48	5
			1	12	4	48	5
west frontage road	structure over I-55	EB	1	12	4	48	5
			1	12	4	48	5
			1	12	4	48	5
structure over I-55	east frontage road	EB	1	12	4	48	5
TOTALS:					44		59
					FT		SY

ROUTE: IL 126 (Van Dyke Rd. to Main St.)							
CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
VAN DYKE RD.	MAIN ST.	EB	1	12	4	48	5
		EB	1	6	50	300	33
		WB	1	12	10	120	13
		WB	1	4	20	80	9
		WB	1	4	20	80	9
TOTALS:					104		70
					FT		SY

FILE NAME =	USER NAME = wilgreendp	DESIGNED -	REVISED -
ca:\work\p\widot\wilgreendp\0183629\0	design.dgn	DRAWN -	REVISED -
PLOT SCALE = 100.0000 "/ IN.	CHECKED -	REVISED -	REVISED -
PLOT DATE = 2/17/2010	DATE -	REVISED -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PATCHING SCHEDULE
BLUFF RD. AND IL 126**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2010-012 R5	WILL	23	15
			CONTRACT NO. 60K31	
FED. ROAD DIST. NO. 1 [ILLINOIS] FED. AID PROJECT				