

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY	ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS	LIGHTING	LOCAL LANDSCAPING	LOCAL WATER MAIN
				100% FED- ARA	80% FED- CMAO 20% LOCAL	70% FED- STP 30% LOCAL	80% FED- CMAO 20% LOCAL	80% FED- CMAO 20% LOCAL	70% FED- STP 30% LOCAL	100% VILLAGE	100% VILLAGE
				CONSTRUCTION TYPE CODE							
				1000-2A	1000-2A	1000-2A	Y031-1F	Y031-1F	Y030-1E	Y003	Y060
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	45	45							
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	515	515							
40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	82	82							
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	125	125							
40701966	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 1/4"	SQ YD	25,937	9,125	16,812						
42001300	PROTECTIVE COAT	SQ YD	7,617			7,617					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	472			472					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	707			707					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	36,914			36,914					
42400800	DETECTABLE WARNINGS	SQ FT	1,140			1,140					
44000100	PAVEMENT REMOVAL	SQ YD	21,816	21,816							
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,019			2,019					
44000300	CURB REMOVAL	FOOT	300			300					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9,491			9,491					
44000600	SIDEWALK REMOVAL	SQ FT	32,687			32,687					
44002211	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 2 3/4"	SQ YD	294	294							
44003100	MEDIAN REMOVAL	SQ FT	754			754					
44201811	CLASS D PATCHES, TYPE 1, 14 INCH	SQ YD	135	135							
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	509	509							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	154	154							
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	82	82							
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	175	175							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	1,228	1,228							
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	448	448							
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	236	236							
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	520	520							

* - DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 VILLAGE OF PALATINE
 PALATINE ROAD & PLUM GROVE ROAD RECONSTRUCTION
 SMITH STREET TO US 14 (NORTHWEST HIGHWAY)
SUMMARY OF QUANTITIES
 SCALE: VERT. _____
 HORIZ. _____
 DATE: OCTOBER 19, 2009
 DRAWN BY: BA
 CHECKED BY: _____

PLOT DATE =
 FILE NAME =
 PLOT SCALE =
 USER NAME =