

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	ROADWAY	ROADWAY	TRAFFIC SIGNALS	TRAFFIC SIGNALS	LIGHTING	LOCAL LANDSCAPING	LOCAL WATER MAIN
				100% FED- ARA	80% FED- CMAO 20% LOCAL	70% FED- STP 30% LOCAL	80% FED- CMAO 20% LOCAL	80% FED- CMAO 20% LOCAL	70% FED- STP 30% LOCAL	100% VILLAGE	100% VILLAGE
				CONSTRUCTION TYPE CODE							
				1000-2A	1000-2A	1000-2A	Y031-1F	Y031-1F	Y030-1E	Y003	Y060
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	18						18		
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	10,097			10,097					
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	3,100			3,100					
X0324007	OPTIMIZE TRAFFIC SIGNAL SYSTEM	EACH	1					1			
X0325239	TEMPORARY PAVEMENT 10"	SQ YD	770			770					
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	4,230			4,230					
X0325837	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 6 INCH	FOOT	9,500			9,500					
X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	800			800					
X04067112	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N70	TON	44	44							
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	25			25					
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	23			23					
X8050010	SERVICE INSTALLATION - GROUND MOUNTED	EACH	1				1				
X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1				1				
X8620020	UNINTERRUPTABLE POWER SUPPLY	EACH	2				2				
X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	1,461					1,461			
X8730027	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C	FOOT	2,055				2,055				
X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1,161				1,161				
XX002264	ELECTRIC CABLE IN CONDUIT, RAILROAD, NO. 14 3C	FOOT	1,116				1,116				
XX002982	GATE VALVES, 6"	EACH	1								1
XX002985	TEMPORARY CAP	EACH	3								3
XX003526	DUCTILE IRON WATER MAIN FITTING - 8"x6" REDUCER	EACH	2								2
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	222			222					
XX005778	DUCTILE IRON WATER MAIN FITTINGS - 45 BEND 8"	EACH	4								4
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	30,334	10,654	19,628				52		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1			1					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5							

\* - DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 VILLAGE OF PALATINE  
 PALATINE ROAD & PLUM GROVE ROAD RECONSTRUCTION  
 SMITH STREET TO US 14 (NORTHWEST HIGHWAY)  
 SUMMARY OF QUANTITIES  
 VERT. SCALE: \_\_\_\_\_  
 HORIZ. SCALE: \_\_\_\_\_  
 DATE: OCTOBER 19, 2009  
 DRAWN BY: BA  
 CHECKED BY: \_\_\_\_\_

PLOT DATE = 09/15/09  
 PLOT TIME = 11:58 AM  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = MUSERN