

SUMMARY OF QUANTITIES

SP	CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY I000-2A			UTILITY ADJUSTMENT Y060	TRAFFIC SIGNALS Y031-1F
					PARTICIPATING 70% FEDERAL / 30% GLEN ELLYN	PARTICIPATING 70% FEDERAL / 30% LOCAL	NON-PARTICIPATING 100% DUPAGE COUNTY	NON-PARTICIPATING 100% GLEN ELLYN	PARTICIPATING 70% FEDERAL / 30% LOCAL
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,109					1,109
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	962					962
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	829					829
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	466					466
*	87301445	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 16 12 PAIR	FOOT	153					153
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	121					121
*	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2					2
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	1					1
*	87601200	PEDESTRIAN PUSH-BUTTON POST, GALVANIZED STEEL, TYPE II	EACH	1					1
*	87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1					1
*	87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1					1
*	87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT.	EACH	1					1
*	87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1					1
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12					12
*	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4					4
* Δ	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	60					60
*	88030020	SIGNAL HEAD, LED, 1-FACE, 3 SECTION, MAST-ARM MOUNTED	EACH	5					5
*	88030050	SIGNAL HEAD, LED, 1-FACE, 3 SECTION, BRACKET MOUNTED	EACH	2					2
*	88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	2					2
*	88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	2					2
*	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED, WITH COUNTDOWN TIMER	EACH	8					8
*	88200100	TRAFFIC SIGNAL BACKPLATE	EACH	7					7
	88600100	DETECTOR LOOP, TYPE I	FOOT	716					716
*	88700200	LIGHT DETECTOR	EACH	2					2
*	88700300	LIGHT DETECTOR AMPLIFIER	EACH	1					1

PLAN
 SUPPRESSED
 PLOTTED
 CHECKED
 BY: _____
 DATE: _____
 NOTE BOOK NO. _____
 FILE NAME _____

PROFILE
 SUPPRESSED
 PLOTTED
 CHECKED
 BY: _____
 DATE: _____
 NOTE BOOK NO. _____
 FILE NAME _____

* INDICATES SPECIALTY ITEM
 Δ DENOTES SPECIAL PROVISION

FILE NAME =	USER NAME = #USER#	DESIGNED - JAB	REVISED - MAP Δ 04/07/10
#FILE#		DRAWN - JMT	REVISED -
	PLOT SCALE = #SCALE#	CHECKED - MAP	REVISED -
	PLOT DATE = #DATE#	DATE - 12/01/2009	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 6 OF 9 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2995	05-00068-00-FP	DUPAGE	141	9
RIFORD ROAD RECONSTRUCTION			CONTRACT NO. 63092	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

