

SUMMARY OF QUANTITIES

SP	CODED PAY ITEM NUMBER	DESCRIPTION	UNIT OF MEASURE	TOTAL QUANTITY	ROADWAY 1000-2A			UTILITY ADJUSTMENT Y060	TRAFFIC SIGNALS Y031-1F
					PARTICIPATING 70% FEDERAL / 30% GLEN ELLYN	PARTICIPATING 70% FEDERAL / 30% LOCAL	NON-PARTICIPATING 100% DUPAGE COUNTY	NON-PARTICIPATING 100% GLEN ELLYN	PARTICIPATING 70% FEDERAL / 30% LOCAL
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	238	171	42	25		
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	74		74			
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	54	46	8			
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	621		621			
	40701801	HOT-MIX ASPHALT PAVEMENT (FULL DEPTH), 6"	SQ YD	8,313	8,313				
	42001300	PROTECTIVE COAT	SQ YD	4,790	3,929	842		19	
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	975	847	86	23	19	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	19,343	14,869	4,474			
	42400800	DETECTABLE WARNINGS	SQ FT	216	192	24			
	44000100	PAVEMENT REMOVAL	SQ YD	9,219	9,133	86			
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	6,742		5,648	1,094		
	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	323		323			
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,350	1,110	183	21	44	
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,462	2,266	1,196			
	44000600	SIDEWALK REMOVAL	SQ FT	6,746	5,145	1,601			
	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	720			720		
	44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	223		223			
	44002218	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4 1/2"	SQ YD	481		311	60	110	
	44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	108	24	10		74	
	44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	354		273	55	26	
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	934		934			
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	181	72	109			
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	74	74				
△	550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	123	123				

\* INDICATES SPECIALTY ITEM  
 △ DENOTES SPECIAL PROVISION

PLAN SURVEYED PLOTTED CHECKED BY DATE  
 NOTE BOOK NO. \_\_\_\_\_  
 STRUCTURE NOTATIONS CHECKED

PROFILE SURVEYED PLOTTED CHECKED BY DATE  
 NOTE BOOK NO. \_\_\_\_\_  
 STRUCTURE NOTATIONS CHECKED

FILE NAME = #FILE#

USER NAME = #USER#

DESIGNED - JAB  
 DRAWN - JMT

REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 2 OF 9 SHEETS STA. TO STA.

F.A.U. RTE. SECTION COUNTY TOTAL SHEET NO.  
 2395 05-00068-00-FP DUPAGE 141 5

RIFORD ROAD RECONSTRUCTION CONTRACT NO. 63092  
 FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT