

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				
ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL	100% FED
				1000-2A
20101200	TREE ROOT PRUNING	EACH	32	32
20800150	TRENCH BACKFILL	CU YD	119	119
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	277	277
25200100	SODDING	SQ YD	277	277
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CU YD	156	156
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	766	766
40600300	AGGREGATE (PRIME COAT)	TON	16	16
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	249	249
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	644	644
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	966	966
42001300	PROTECTIVE COAT	SQ YD	1741	1741
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	61	61
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1086	1086
42400800	DETECTABLE WARNINGS	SQ FT	100	100
44000100	PAVEMENT REMOVAL	SQ YD	1136	1136
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	7641	7641
44000600	SIDEWALK REMOVAL	SQ FT	1086	1086
44000700	APPROACH SLAB REMOVAL	SQ YD	130	130
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1026	1026
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	23	23
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	25	25
50300225	CONCRETE STRUCTURES	CU YD	19	19
50300255	CONCRETE SUPERSTRUCTURE	CU YD	68	68
50300260	BRIDGE DECK GROOVING	SQ YD	205	205
50300300	PROTECTIVE COAT	SQ YD	205	205
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	16482	16482
50800515	BAR SPLICERS	EACH	162	162
550B0320	STORM SEWERS, CLASS B, TYPE 2 8"	FOOT	208	208
55100300	STORM SEWER REMOVAL 8"	FOOT	208	208
60202705	CATCH BASINS, TYPE A, 4'-DIAMETER, WITH SALVAGED FRAME AND GRATE	EACH	12	12

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL	100% FED
				1000-2A
60238500	INLETS, TYPE A, WITH SALVAGED FRAME AND GRATE	EACH	4	4
60250200	CATCH BASINS TO BE ADJUSTED	EACH	16	16
60253000	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1
60255500	MANHOLES TO BE ADJUSTED	EACH	12	12
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	9	9
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2
60266300	VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1
60266600	VALVE BOXES TO BE ADJUSTED	EACH	4	4
60500050	REMOVING CATCH BASINS	EACH	12	12
67100100	MOBILIZATION	L SUM	1	1
70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	520	520
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	496	496
* 78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	139	139
* 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	132	132
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	35	35
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	343	343
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	40	40
K1005881	TREE TRUNK PROTECTION	EACH	10	10
X0323389	STORM SEWER CONNECTION	EACH	17	17
LR420033	PORTLAND CEMENT CONCRETE PAVEMENT, 9" (SPECIAL)	SQ YD	1161	1161
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0017099	DOWEL BAR ASSEMBLY	EACH	23	23
Z0017202	DOWEL BARS 1 1/2"	EACH	23	23
* DENOTES SPECIALTY ITEM				