

**SUMMARY OF QUANTITIES**

	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
					ROADWAY 1000-1A	SIGNALS Y031-1F	SIDEWALK Y044
**	28000305	TEMPORARY DITCH CHECKS	FOOT	10	10		
**	28000400	PERIMETER EROSION BARRIER	FOOT	95	95		
**	28000510	INLET FILTER	EACH	2	2		
x **	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SO YD	133	133		
x **	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2	2		
x **	42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SO FT	949	949		
x **	42400800	DETECTABLE WARNINGS	SO FT	80	80		
x **	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	94	94		
x **	44004700	SIDEWALK REMOVAL (SPECIAL)	SO FT	444	444		
	67100100	MOBILIZATION	L SUM	1	1		
x	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
x	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
x	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
x	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	16	16		
	72000100	SIGN PANEL, TYPE 1	SO FT	64.5	36	28.5	
x	72400100	REMOVE SIGN PANEL ASSEMBLY, TYPE A	EACH	5	5		
	72900100	METAL POST, TYPE A	FOOT	100	100		
**	78000400	THERMOPLASTIC PAVEMENT MARKING, LINE 6"	FOOT	608	608		
**	78000600	THERMOPLASTIC PAVEMENT MARKING, LINE 12"	FOOT	169	169		
**	78000650	THERMOPLASTIC PAVEMENT MARKING, LINE 24"	FOOT	140	140		
x	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	584		584	
	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	28.5		28.5	
	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	8		8	
	81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	10		10	
	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	71		71	
	81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	87		87	
	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	336		336	
	81019000	CONDUIT PUSHED, 5" DIA., GALVANIZED STEEL	FOOT	28		28	
	81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	4		4	
	81400710	HEAVY DUTY HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5		5	
	81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	2		2	
	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	934		934	
	85700200	FULL - ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1	
	86200200	UNITERRUPTABLE POWER SUPPLY, STANDARD	EACH	1		1	
	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	1316		1316	
	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	1904		1904	
	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	921		921	
	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	1760		1760	
	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1884		1884	
	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6, 2C	FOOT	95		95	
	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	3		3	

\*\* DENOTES SPECIALTY ITEMS  
x DENOTES ITEMS REFERENCED IN A SPECIAL PROVISION

Revised 12-14-09

COPYRIGHT © 2005 BY BAXTER & WOODMAN, INC.  
 DRAWN BY: BCD  
 LICENSE NO. 184-0010 - EXPIRES 4/30/2011  
 10/15/2009 9:06:05 AM  
 \\corp.baxwood.com\corp\electr\mokeno\litch\071621-soq.sht



DESIGNED - NJP	REVISED - PER COUNTY 8-20-09
DRAWN - BCD	REVISED - PER IDOT 09-16-09
CHECKED - RWL	REVISED -
DATE - 06-25-09	FILE - 071621-soq.sht

**WILL COUNTY DEPARTMENT OF HIGHWAYS  
 LARAWAY ROAD AT WOLF ROAD**

**SUMMARY OF QUANTITIES**

SCALE: STA. TO STA.

F.A.U. RTE. 320	SECTION 07-00138-26-TL	COUNTY WILL	TOTAL SHEETS 19	SHEET NO. 4
C-91-405-08		CONTRACT NO. 63329		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				