

**SUMMARY OF QUANTITIES**

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 1000-1A	SIGNALS Y031-1F	SIDEWALK Y044
87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	1		1	
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1		1	
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	1		1	
87700310	STEEL MAST ARM ASSEMBLY AND POLE, 54 FT.	EACH	1		1	
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12		12	
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4	
87800400	CONCRETE FOUNDATION, TYPE E 30" DIAMETER	FOOT	15		15	
87800415	CONCRETE FOUNDATION, TYPE E 36" DIAMETER	FOOT	45		45	
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4		4	
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4		4	
88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4		4	
88102710	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	6		6	
88102740	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED	EACH	1		1	
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	8		8	
88500100	INDUCTIVE LOOP DETECTOR	EACH	8		8	
88600100	DETECTOR LOOP, TYPE 1	FOOT	1052		1052	
88700200	LIGHT DETECTOR	EACH	2		2	
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1	
x 88800100	PEDESTRIAN PUSH BUTTON	EACH	7		7	
X8050015	SERVICE INSTALLATION, POLE MOUNTED	EACH	1		1	
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	1173		1173	
X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FOOT	330		330	

•• DENOTES SPECIALTY ITEMS  
x DENOTES ITEMS REFERENCED IN A SPECIAL PROVISION

Revised 12-14-09

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC. 15164 Main Street, Woodman, IL 61890  
 LICENSE NO. 184-00129 - EXPIRES 4/30/2011  
 \\corp.baxwood.com\p\01621\soq\01621-soq.sht  
 10/15/2009 8:55:42 AM



DESIGNED - NJP	REVISED - PER COUNTY 8-20-09
DRAWN - BCD	REVISED - PER IDOT 09-16-09
CHECKED - RWL	REVISED -
DATE - 06-25-09	FILE - 071621-soq.sht

**WILL COUNTY DEPARTMENT OF HIGHWAYS  
 LARAWAY ROAD AT WOLF ROAD**

**SUMMARY OF QUANTITIES**

SCALE: STA. TO STA.

F.A.U. R/E.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	07-00138-26-TL	WILL	19	5
C-91-405-08			CONTRACT NO. 63329	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				