



LEGEND:

- x - x - TEMPORARY FENCE
- TREE PROTECTION
- ROOT PRUNING
- ▨ REMOVE AGGREGATE PATH (EARTH EXCAVATION)
- ▩ PAVEMENT REMOVAL
- ✕ TREE OR STREET FURNITURE REMOVAL
- D DONATION BENCH (SEE GENERAL NOTES)
- S SALVATION BENCH (SEE GENERAL NOTES)
- CURB REMOVAL

- NOTES:**
1. THE CITY OF EVANSTON WILL PERFORM ALL TREE BRANCH PRUNING. THE CONTRACTOR MUST COORDINATE WITH THE ENGINEER IF THIS WORK IS REQUIRED.
 2. SEE EROSION CONTROL PLANS AND LANDSCAPE PLANS FOR TEMPORARY TREATMENT AND PERMANENT RESTORATION OF AREAS DISTURBED BY REMOVALS.
 3. RELOCATE EXISTING CONCRETE PARKING BUMPERS ON THE EAST SIDE OF THE PARKING LOT 3.5 FT TO 5.5 FT WEST. PARKING BUMPERS SHOULD BE PLACED 1.5 FT FROM THE WEST EDGE OF THE PROPOSED BICYCLE PATH. SEE SHEET 24.
 4. SEE DETAIL ON SHEET 41 FOR CURB REMOVAL FOR PROPOSED ADA CURB RAMPS.

AECOM	USER NAME = ozonjhab	DESIGNED - BMC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	REMOVAL PLAN	F.A. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
	PLOT SCALE =	CHECKED - SLW	REVISED -			07-00246-00-BT	COOK	81	14
	PLOT DATE = 12/01/2009	DATE = 12/01/2009	REVISED -			ITP NO. 102121	CONTRACT NO. 63423		
						SCALE: 1"=20'	SHEET NO. OF SHEETS	STA. 67+50 TO STA. 73+50	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

12/01/2009 \\ussc01p207\p600995\6\1000\cadd\01\erwin\p600995\sheet\04_09133907.dht+rem_04.dgn

C-91-338-07