



**LEGEND:**

	REMOVE AGGREGATE PATH (EARTH EXCAVATION)		TREE PROTECTION
	PAVEMENT REMOVAL		TEMPORARY FENCE
	TREE OR STREET FURNITURE REMOVAL		ROOT PRUNING
	DONATION / SALVAGE BENCH (SEE GENERAL NOTES)		
	CURB REMOVAL		

- NOTES:**
1. THE CITY OF EVANSTON WILL PERFORM ALL TREE BRANCH PRUNING. THE CONTRACTOR MUST COORDINATE WITH THE ENGINEER IF THIS WORK IS REQUIRED.
  2. SEE EROSION CONTROL PLANS AND LANDSCAPE PLANS FOR TEMPORARY TREATMENT AND PERMANENT RESTORATION OF AREAS DISTURBED BY REMOVALS.
  3. WORK FOR "RELOCATE EXISTING PICNIC AREA" INCLUDES THE REMOVAL AND REINSTALLATION OF PICNIC AREA SIGNAGE, GRILLS, AND FIREPITS. REMOVAL OF TIMBERS AND AGGREGATE PAVEMENT WILL BE PAID FOR UNDER EARTH EXCAVATION.

12/01/2009 \\nascent\j2007\p60099576\p60099576\900\_cad\901\_drawing\p60099576.dgn  
 12/01/2009 \\nascent\j2007\p60099576\p60099576\900\_cad\901\_drawing\p60099576.dgn

<b>AECOM</b>	USER NAME = ozonykab	DESIGNED - BMC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REMOVAL PLAN</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	CHECKED - SLW	REVISED -			07-00246-00-BT	COOK	81	16	
	PLOT DATE = 12/01/2009	DATE - 12/01/2009	REVISED -	SCALE: 1"=20'	SHEET NO. OF SHEETS	STA. 80+00 TO STA. 86+00	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 63423	

C-91-338-07