

EARTH EXCAVATION SCHEDULE

PAY ITEM DESCRIPTION	QUANTITY	UNIT	EXCAVATION COMPUTATION FACTORS	EARTHWORK VOLUME CU YD
PCC BASE COURSE 10"	1:38	SQ YD	*9*0.5/27	190
PORTLAND CEVENT CONCRETE BASECOURSE WIDENING 10"	664	SQ FT	SF*1.83'/27	45
PORTLAND CEVENT CONCRETE DRIVEWAYPAVEMENT, 8"	1312	SQ YD	SY*9*0.5/27	219
PCC SIDEWALK 5 INCH, SPECIAL	2437	SQ YD	SY*9*0.5/27	2437
CONCRETE CURB, TYPE B	200	LF	LF*1.5SF/27	11
COMBINATION CONCRETE AND GUTTER, (SPECIAL)	18961	LF	L*1.0*0.5 *L*1.25*2.0 -3.0L/27	2106
PORTLAND CEVENT CONCRETE PAVEMENT (SPECIAL)	2215	SQ YD	SY*9*0.5/27	369
CONCRETE PAVER SIDEWALK	2640	SQ YD	SY*9*3.5/12/27	257
SANITARY SEWER PVC SDR 26 R (WATER MAIN QUALITY), 8"	2191	FOOT	SEWER SCHEDULE	1695
STORM SEWERS, TYPE I, WATER MAIN QUALITY PIPE, 12"	2528	FOOT	SEWER SCHEDULE	2160
TOTAL				9489

NOTE: EARTHWORK FOR PLANTER CURB, PLANTER WALL AND ALL OTHER PAY ITEMSS IS INCLUDED WITHIN EACH INDIVIDUAL PAY ITEM

REMOVAL PLAN SHEET NUMBER	20100110 TREE REMOVAL (6 TO 15 UNITS DIA EACH)	40600982 HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT SQ YD	44000100 PAVEMENT REMOVAL SQ YD	44000198 HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH SQ YD	44000200 DRIVEWAY PAVEMENT REMOVAL SQ YD	44000500 COMBINATION CURB AND GUTTER REMOVAL FOOT
1	0	66	449	2338	92	889
2	0	36	286	3016	176	1233
3	0	38	275	2619	162	1015
4	0	35	407	2445	57	1049
5	0	71	776	2889	56	1305
6	0	46	328	2685	52	1081
7	0	72	749	2748	120	1290
8	0	73	461	3092	117	1441
9	0	26	266	2960	51	1209
10	0	11	151	2556	55	980
11	40	89	382	2989	115	1243
12	0	74	434	3053	44	1320
13	0	32	316	2593	44	1053
14	0	54	310	3278	114	1296
15	0	63	188	2466	34	982
TOTAL	40	786	5,779	41,727	1,289	17,395

REMOVAL PLAN SHEET NUMBER	44000600 SIDEWALK REMOVAL SQ FT	44002000 CONCRETE CURB REMOVAL FOOT	44201325 CLASS C PATCHES TYPE I 8 INCH SQ YD	44201329 CLASS C PATCHES TYPE II 8 INCH SQ YD	44201737 CLASS D PATCHES TYPE I 8 INCH SQ YD	44201741 CLASS D PATCHES TYPE II 8 INCH SQ YD	44201745 CLASS D PATCHES TYPE III 8 INCH SQ YD	44201747 CLASS IV PATCHES TYPE IV 8 INCH SQ YD
1	3265	4	0	0	4	14	17	0
2	6308	0	0	0	0	0	20	0
3	6344	0	0	0	0	0	17	56
4	7172	14	0	0	0	0	35	58
5	8563	10	3	11	0	0	34	131
6	6858	0	0	0	0	0	0	46
7	7101	17	4	0	0	12	12	74
8	8237	0	0	0	0	0	35	74
9	8600	0	0	0	0	0	0	0
10	6874	0	0	0	0	0	0	0
11	7223	0	0	0	0	0	0	0
12	9371	0	0	0	0	0	18	139
13	7096	0	0	0	0	12	21	0
14	7044	0	0	0	0	0	27	0
15	6407	0	0	0	0	7	0	0
TOTAL	106,463	45	7	11	4	44	237	577

PLAN AND PROFILE SHEET NUMBER	DRIVEWAY LOCATION STA.	42300400 PCC DRIVEWAY PAVT 8" (SQ YD)
1	100+80.54	6.97
	101+00.39	53.67
	101+38.09	12.71
	101+71.68	31.34
2	105+14.62	21.35
	105+26.90	16.26
	105+85.22	20.95
	105+91.60	23.92
	107+72.53	20.13
	108+11.65	16.26
	108+31.10	16.35
	109+04.63	16.26
	109+68.70	20.87
3	110+52.20	62.95
	110+96.44	28.97
	111+63.32	24.07
	112+18.77	28.35
	114+73.84	13.94
4	115+16.90	29.04
	119+50.20	11.39
5	123+06.54	12.84
	124+23.91	24.55
	125+52.46	18.84
6	128+90.13	24.37
	129+32.35	22.96
7	131+17.47	15.54
	133+10.49	15.78
	133+37.18	27.22
	134+45.92	22.05
	135+99.87	23.09
8	137+26.32	25.71
	137+76.84	15.58
	139+53.01	32.71
	140+76.08	22.60
	142+39.00	17.24
9	143+83.49	10.81
	143+99.63	37.90
10	153+46.70	31.28
	153+82.97	30.03
11	154+35.08	37.79
	155+75.68	24.19
	155+87.37	24.76
	158+99.22	20.30
12	160+76.89	12.85
	162+95.36	12.75
	163+31.68	17.87
13	167+07.32	11.91
	169+19.44	15.30
	170+72.78	17.32
14	171+31.30	14.33
	172+62.25	12.66
	174+18.03	22.39
	174+57.48	15.59
	175+77.13	17.02
	176+23.27	16.58
	176+80.17	14.99
15	177+56.15	15.05
	179+98.82	18.43
TOTAL		1,249

FILE NAME = DIRTE38-sht-schedule97.dgn

USER NAME = IDDT

PLLOT SCALE = 20.0000' / IN.
PLLOT DATE = 3/11/2010

DESIGNED - BB
DRAWN - TM
CHECKED - JB
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: 1" = 20' SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
347	09-00248-00-RS	COOK	274	5
CONTRACT NO. 63432				
ILLINOIS FED. AID PROJECT				