







NOTES

1. ALL TREES NOT BEING REMOVED SHALL BE PROTECTED AT ALL TIMES. EXACT TREES WILL BE DETERMINED IN THE FIELD BY THE ENGINEER AND WILL BE PAID FOR AS "TREE TRUNK PROTECTION" OR "TEMPORARY FENCE".
2. THE VARIABLE DEPTH STONE PARKING LOT WILL BE REMOVED AND DISPOSED OF AT THE SOUTH-END FACILITY AT DUNDEE ROAD (AT THE SOUTHERN LIMITS OF THE CHICAGO BOTANIC GARDEN). HAULING AND DISPOSAL IS INCLUDED WITHIN THE PAY ITEM, "EARTH EXCAVATION, SPECIAL".
3. WHEN TRANSPLANTING TREES TO FINAL LOCATIONS, THE TREES SHALL BEAR THE SAME RELATIONSHIP TO GRADE AS THEY DID PRIOR TO TRANSPLANTING. THE LOCATION AND ORIENTATION OF THE RE-PLANTED TREES SHALL BE DETERMINED BY THE ENGINEER.
4. SEE NORTH-END IRRIGATION PLAN FOR EXISTING 2" PVC PIPE TO BE REMOVED.

DEMOLITION LEGEND

-  EXISTING STONE PARKING LOT TO BE REMOVED
-  DRIVEWAY PAVEMENT REMOVAL
-  EXISTING CURB AND GUTTER TO BE REMOVED
-  EXISTING STORM SEWER TO BE REMOVED
-  EXISTING INLET TO BE REMOVED
-  EXISTING TREE TO BE TRANSPLANTED



FILE NAME = 49105_sht_demo-clc.dgn	USER NAME = lsupencheck	DESIGNED - LLS	REVISED - ---
		DRAWN - LLS	REVISED - ---
		CHECKED - KJK	REVISED - ---
DESIGNED BY HNTB	PLOT DATE =	DATE - 02/16/2010	REVISED - ---

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**CHICAGO BOTANIC GARDEN - CLC ENTRYWAY
NORTH-END EXISTING CONDITIONS AND DEMOLITION PLAN**

SCALE: 1"=30' SHEET NO. XX OF XX SHEETS STA. N/A TO STA. N/A

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	08-00061-00-RS	COOK	28	7
FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT			CONTRACT NO. 63449	