SUMMARY OF QUANTITIES

100% STATE
SFTY-2A
URBAN

PAY ITEM #	DESCRIPTION	UNIT	QUANTITY
40603570	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90	TON	140
42001300	PROTECTIVE COAT	SQ YD	261
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1608
50102400	CONCRETE REMOVAL	CU YD	116.8
50300255	CONCRETE SUPERSTRUCTURE	CU YD	117.4
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	13,080
50800515	BAR SPLICERS	EACH	168
52000110	PREFORMED JOINT STRIP SEAL	FOOT	714
67100100	MOBILIZATION	L SUM	1
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	2
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30,200
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	10,110
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2,500
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2,200
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	14,236
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,500
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1
X7030020	TEMPORARY PAVEMENT MARKING TAPE, 8 INCH (BLACK)	FOOT	300
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	6
Z0030280	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE,NARROW), TEST LEVEL 3	EACH	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4

* SPECIALTY ITEM