

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	36 BR	IROUOIS	21	3
STA. 1248+00		TO STA.1254+50		
FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT				

CONTRACT NO. 66171

SUMMARY OF QUANTITIES					
CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANT.	CONSTRUCTION TYPE CODE	
				I000	X028-2A
20200100	EARTH EXCAVATION	CU YD	350	350	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	620	620	
25000200	SEEDING, CLASS 2	ACRE	0.5	0.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45	45	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45	45	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45	45	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50	50	
28000305	TEMPORARY DITCH CHECKS	FOOT	80	80	
31100300	SUB-BASE GRANULAR MATERIAL,TYPE A 4"	SQ YD	285	285	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	160	160	
40600300	AGGREGATE (PRIME COAT)	TON	4	4	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1477	1477	
44000100	PAVEMENT REMOVAL	SQ YD	273	273	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	908	908	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50800105	REINFORCEMENT BARS	POUND	31640		31640
51205200	TEMPORARY SHEET PILING	SQ FT	1105		1105
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	174.7		174.7
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	550	550	
* 63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	75		75
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	454	454	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
28100107	STONE RIPRAP, CLASS A 4	SQ YD	98		98
28200200	FILTER FABRIC	SQ YD	98		98
28000400	PERIMETER EROSION BARRIER	FOOT	900	900	
25100630	EROSION CONTROL BLANKET	SQ YD	2500	2500	

SUMMARY OF QUANTITIES					
CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANT.	CONSTRUCTION TYPE CODE	
				I000	X028-2A
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	11	11	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1950	1950	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1300	1300	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	170	170	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	325	325	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	325	325	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	275	275	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1300	1300	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	170	170	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	9	9	
* 78200405	GUARDRAIL MARKERS	EACH	12	12	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	62	62	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9	9	
X0321100	GEOTEXTILE RETAINING WALL	SQ FT	94		94
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	267	267	
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"	SQ YD	129	129	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	150	150	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	97	97	
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1	
50800515	BAR SPLICERS	EACH	154		154
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. NONE
HORIZ. NONE

DATE _____ DRAWN BY _____
CHECKED BY _____