

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-3)HBK	LASALLE	492	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90/10 FED/ST CONSTRUCTION CODES			
				J000	X271-2A	Y030-1E	100% CITY J000
				28100107	STONE RIPRAP, CLASS A4	SQ YD	392
28200200	FILTER FABRIC	SQ YD	392	392			
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	8,089	8,089			
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	46,799	46,799			
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	8490	8,490			
31200500	STABILIZED SUB BASE - HOT-MIX ASPHALT, 4"	SQ YD	40518	40,518			
35100100	AGGREGATE BASE COURSE, TYPE A	TON	3873	2,408			1,465
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	73	73			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	632	632			
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	25,022	24,111			911
40600895	CONSTRUCTING TEST STRIP	EACH	2	2			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	777	507			270
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	593	413			180
40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	SQ YD	7194	7,194			
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	28537	28,537			
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	413	413			
42001300	PROTECTIVE COAT	SQ YD	26347	26,347			
42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	48	48			

* SPECIALTY ITEMS

Copyright Hanson Professional Services Inc. 2009, YEARS
HANSON
 Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2888
 Offices Nationwide

MODEL NAME = #MODEL
 PLOT DATE = Feb 17, 2010 - 02:57:05 PM
 FILE NAME = c:\p\work\66542\PROJECT\RDJ\SUMMARY.dgn
 PLOT SCALE = 50.0000 / IN.
 USER NAME = carter@hanson

LAYOUT	RDJ	12/14/05
DRAWN	RDJ	12/14/05
REVIEWED	MTM	10/17/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES -2

SCALE: VERT. N/A
 HORIZ. N/A

DATE _____ DRAWN BY RDJ
 CHECKED BY _____