

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-3)HBK	LASALLE	492	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITIY	90/10 FED/ST CONSTRUCTION CODES			100% CITY J000
				J000	X271-2A	Y030-1E	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	307	307			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	657	657			
44000100	PAVEMENT REMOVAL	SO YD	26866	26,866			
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	1205	1,205			
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	856	856			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1026	1,026			
44003100	MEDIAN REMOVAL	SO FT	4987	4,987			
44004250	PAVED SHOULDER REMOVAL	SO YD	17,036	17,036			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4,856	4,856			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SO YD	279	279			
48203052	HOT-MIX ASPHALT SHOULDERS, 13 3/4"	SO YD	12,648	12,648			
48300415	PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	SO YD	11539	11,539			
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1		
50105220	PIPE CULVERT REMOVAL	FOOT	1,264	1,264			
50157300	PROTECTIVE SHIELD	SO YD	1287		1,287		
50200100	STRUCTURE EXCAVATION	CU YD	523	523			
50300225	CONCRETE STRUCTURES	CU YD	210		210		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	412		412		
50300260	BRIDGE DECK GROOVING	SO YD	1137		1,137		

* SPECIALTY ITEMS

MODEL NAME = #MODEL#
 PLOT DATE = Feb 17, 2010 - 02:57:51 PM
 FILE NAME = c:\pwworkspace\PROJECTS\INTERCOM\1493\Revised Summary.dgn
 USER NAME = ComputerJ
 LAYOUT: RDJ 12/14/05
 DRAWN: RDJ 12/14/05
 REVIEWED: MTM 10/1/07

HANSON
 Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Offices Nationwide

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES -3

SCALE: VERT. N/A
 HORIZ. N/A
 DATE

DRAWN BY RDJ
 CHECKED BY