

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-3)HBK	LASALLE	492	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90/10 FED/ST CONSTRUCTION CODES			
				J000	X271-2A	Y030-1E	100% CITY J000
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	199	199			
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	136	136			
550A4500	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND - SIZE 36"	FOOT	42	42			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	118		118		
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	27	27			
60100945	PIPE DRAINS 12"	FOOT	246	246			
60107600	PIPE UNDERDRAINS 4"	FOOT	13770	13,770			
60107700	PIPE UNDERDRAINS 6"	FOOT	3238	3,238			
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	513	513			
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	62	62			
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	215		215		
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	4	4			
60221000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1			
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60500060	REMOVING INLETS	EACH	13	13			
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	998	998			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	13017	13,017			
60621900	CONCRETE MEDIAN, TYPE SM (SPECIAL)	SQ FT	360	360			

* SPECIALTY ITEMS

© Copyright Hanson Professional Services Inc. 2009. YEARS
HANSON
 Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Offices Nationwide

MODEL NAME = #MODEL#
 PLOT DATE = Feb 17, 2018 - 02:57:24 PM
 FILE NAME = c:\p\work\p\DOT\CORPENTER\J\dm1493\Revised Summary.dgn
 PLOT SCALE = 30.0000 / 1" = 100.0000'
 USER NAME = corpenardj

2	LAYOUT	RDJ	12/14/05
	DRAWN	RDJ	12/14/05
	REVIEWED	MTN	10/2/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES -6

SCALE: VERT. N/A
 HORIZ. N/A

DATE

DRAWN BY RDJ
 CHECKED BY