

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-3)HKB	LASALLE	492	15
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90/10 FED/ST			
				CONSTRUCTION CODES			
				J000	X271-2A	Y030-1E	100% CITY J000
* 83502400	LIGHT TOWER, 100 FT. MOUNTING HEIGHT, LUMINAIRE MT. - 6	EACH	17			17	
* 83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	9			9	
* 83700300	LIGHT TOWER FOUNDATION, 48" DIAMETER	FOOT	310			310	
* 83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	36			36	
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	22			22	
* 84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	17			17	
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	16			16	
* 84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1			1	
* 84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	1			1	
* 84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1			1	
X0320139	TEMPORARY CONSTRUCTION FENCE	FOOT	300	300			
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	41	41			
X0323411	REMOVE EXISTING LIGHTING CONTROLLER AND CONC FOUNDATION	EACH	1			1	
X0324590	INLET BOX FOR 24" PIPE	EACH	2	2			
X0324752	STORM SEWER TO BE FILLED	CU YD	10	10			
X0325969	PORTABLE VEHICLE MOUNTED CHANGEABLE MESSAGE BOARD	CAL DA	40	40			
X0712400	TEMPORARY PAVEMENT	SO YD	20,593	20,593			
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	1877	1877			

* SPECIALTY ITEMS

© Copyright Hanson Professional Services Inc. 2005, 2006, 2007



Hanson Professional Services Inc.
1525 South Sixth Street
Springfield, Illinois 62703-2886
Offices Nationwide

MODEL NAME = #MODEL#
PLOT DATE = Feb 17, 2018 - 02:56:37 PM
FILE NAME = c:\p\work\PM\DOT\CARPENTER\RDJ\sum14193\Revised Summary.dgn
PLOT SCALE = 50:0000 / 1" = 50'-0" / 1"
USER NAME = carpenterj

LAYOUT	RDJ	12/14/05
DRAWN	RDJ	12/14/05
REVIEWED	MTM	10/1/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES -12

SCALE: VERT. N/A
HORIZ. N/A

DATE

DRAWN BY RDJ
CHECKED BY