

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	150-31HBK	LASALLE	492	31
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVING SCHEDULE-2

LOCATION	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	AGGREGATE BASE COURSE, TYPE A	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/4"	HOT-MIX ASPHALT SHOULDERS, 13 3/4"	HOT-MIX ASPHALT SHOULDERS, 6"	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	PORTLAND CEMENT CONCRETE SHOULDERS 9 3/4"	HOT-MIX ASPHALT SURFACE COURSE MIX D N70
	(SQ YD)	(SQ YD)	(SQ YD)	(TON)	(SQ YD)	(GAL)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(SQ YD)	(TON)
IL RTE 178												
STA 96+00.00 RT & LT TO 108+82.80 RT & LT		8519.3				2944.42				5507.6		
STA 90+47.10 RT & LT TO 96+12.16 RT & LT												
STA 96+00.00 19.50 RT TO 108+82.80 35.00 RT											1058.2	
STA 96+00 TO 108+82.80 RT & LT					7851.8							
STA 96+00.00 19.50 LT TO 108+82.80 23.00 LT											1140.2	
STA 110+87.31 RT & LT TO 113+73.50 RT & LT		2003.0			1823.3	751.25				1314.5		
STA 110+87.31 23.00 RT TO 113+58.50 23.00 RT											241.1	
STA 110+87.31 23.00 LT TO 113+58.50 23.00 LT											241.1	
STA 111+76.45 31.00 RT TO 114+03.50 31.00 RT								81.8				
STA 112+59.84 31.00 LT TO 114+03.50 31.00 LT								63.9				
STA 115+96.50 31.00 RT TO 117+40.12 31.00 RT								51.9				
STA 115+96.50 31.00 LT TO 118+23.57 31.00 LT								81.8				
STA 116+26.50 RT & LT TO 119+40.36 RT & LT		2197.0			1994.3	823.87				1436.3		
STA 116+41.50 23.00 RT TO 119+40.36 23.00 RT											265.7	
STA 116+41.50 23.00 LT TO 119+40.36 23.00 LT											265.7	
STA 121+28.13 RT & LT TO 124+83.77 RT & LT		2806.2			2401.8	900.67				2041.8		
STA 121+28.13 35.00 LT TO 124+83.78 23.18 LT											158.2	
STA 121+28.14 23.02 RT TO 124+83.78 35.00 RT											162.2	
STA 126+84.37 RT & LT TO 136+67.36 RT & LT		5751.0			5005.7	1877.13				3139.7		
STA 126+84.37 23.00 LT TO 136+67.36 12.28 LT											873.7	
STA 126+84.38 23.00 RT TO 136+67.36 11.72 RT											808.3	
STA 136+67.34 TO 141+55.00								867.0				107
								867.0	279.3	13439.8	5214.3	107.3
FRONTAGE ROAD												
STA 604+59.57 TO 621+56.37						2195.0						486
STA 604+79.57 TO 621+56.37				3873.0								
				3873.0		2195.0						486
IL RTE 178 INTERSECTIONS												
RAMPS K & L		2754.2			2386.9	1032.77				2027.8	358.9	
RAMPS I & J		2457.1			2130.9	921.35				1808.2	322.7	
FRONTAGE ROAD		2227.2			2152.3	807.13				1977.7	154.8	
		7438.5			6670.2	2761.24				5813.7	836.4	
TOTAL	8089	46799	8490	3873	40518	25022	7194	12648	279	28537	11539	593

GUARDRAIL AND TRAFFIC BARRIER TERMINAL SCHEDULE

LOCATION	STEEL PLATE BEAM GUARD RAIL, TYPE A	TRAFFIC BARRIER TERMINAL, TYPE 2	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	TERMINAL MARKER - DIRECT APPLIED
	FOOT	EACH	EACH	EACH	EACH
IL RTE 178					
STA 112+09.85 32.50 RT				1	1
STA 112+59.84 31.00 LT		1			
STA 112+59.85 31.00 RT TO 113+72.35 31.00 RT	112.5				
STA 112+72.34 31.00 LT TO 113+72.34 31.00 LT	100				
STA 113+72.34 31.00 LT			1		
STA 113+72.35 31.00 RT			1		
STA 115+96.37 31.00 RT			1		
STA 115+96.37 31.00 LT			1		
STA 116+27.62 31.00 RT TO 117+27.62 31.00 RT	100				
STA 116+27.62 31.00 LT TO 117+40.12 31.00 LT	112.5				
STA 117+40.12 31.00 RT		1			
STA 117+90.12 32.50 LT				1	1
TOTAL	425	2	4	2	2

SHOULDER RUMBLE STRIP SCHEDULE

LOCATION	SHOULDER RUMBLE STRIP
	FOOT
I-80	
STA 866+05.68 22.34 LT TO 915+00.00 22.34 LT	4894
STA 869+57.86 22.34 RT TO 915+00.00 22.34 RT	4542
STA 883+04.68 49.38 LT TO 886+13.82 49.37 LT	309
STA 883+11.86 49.94 RT TO 887+30.05 49.96 RT	418
STA 905+20.05 49.29 LT TO 908+59.83 49.27 LT	340
STA 905+55.87 50.03 RT TO 908+81.07 50.05 RT	325
STA 19+08.45 22.34 LT TO 24+98.57 22.34 LT	590
STA 19+08.45 22.34 RT TO 30+89.60 22.34 RT	1181
TOTAL	12600

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES-5

SCALE: VERT. N/A
HORIZ. N/A

DATE: _____ DRAWN BY RDJ
CHECKED BY _____

© Copyright Hanson Professional Services Inc. 2009
HANSON
 Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Offices Nationwide

MODEL NAME = Sheet_05
 PLOT DATE = 12/23/2009
 PLOT SCALE = 50/8000
 USER NAME = Johna00944
 LAYOUT: RDJ 01/20/06
 DRAWN: RDJ 01/20/06
 REVIEWED: MTM 10/1/07