

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(50-3)HBK	LASALLE	492	37
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVEMENT MARKING IL-178 SCHEDULE 4 AND TOTALS					THERMOPLASTIC PAVEMENT MARKING - LINE 4"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"
					(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
<b>IL RTE 178</b>													
STA	121+51.93	28.31'	LT	RIGHT TURN ARROW				15.6					
STA	122+50.16	28.38'	LT	RIGHT TURN ARROW				15.6					
STA	122+67.08	23.00'	LT	TO 124+83.77 23.00'	LT						54.2		
STA	123+47.91	23.00'	RT	TO 125+62.91 23.00'	RT						215.0		
STA	123+58.24	28.97'	RT	RIGHT TURN ARROW				15.6					
STA	123+63.61	9.00'	RT	TO 125+62.91 9.00'	RT						199.3		
STA	123+86.52	3.87'	RT	LEFT TURN ARROW				15.6					
STA	124+42.91	28.49'	RT	RIGHT TURN ARROW				15.6					
STA	124+62.16	3.72'	RT	LEFT TURN ARROW				15.6					
STA	124+83.77	23.18'	LT	TO 125+87.43 116.02'	LT				167.7				
STA	125+14.13	28.65'	RT	RIGHT TURN ARROW				15.6					
STA	125+35.81	3.79'	RT	LEFT TURN ARROW				15.6					
STA	125+60.91			STOP BAR									12.0
STA	125+62.91	3.00'	LT	TO 125+62.91 9.00'	LT				9.4				
STA	126+06.75	121.19'	LT	TO 126+84.37 23.00'	LT				133.8				
STA	126+77.36	5.28'	LT	TO 126+78.39 9.00'	LT				5.2				
STA	126+77.36	5.28'	LT	TO 134+52.15 0.00'	RT				774.8				
STA	126+78.39	9.00'	LT	TO 134+52.15 0.00'	RT				773.8				
STA	126+84.37	23.00'	LT	TO 136+67.36 12.28'	LT				983.0				
STA	134+52.15	0.00'	CL	TO 139+57.18 0.00'	CL				505.0				
STA	134+57.18	0.50'	RT	TO 139+57.18 1.30'	RT					125.0			
STA	125+47.52	23.00'	LT	TO 125+97.86 24.00'	LT						50.0		
<b>FRONTAGE ROAD TOTALS (SEE SCHEDULE 3 THIS SHEET)</b>								15.6	501.0	93.0	65.0	42.0	
<b>PROJECT TOTAL</b>					22,409	2,802	4,104	702	28,590	690	2,464	229	172

RAISED REFLECTIVE PAVEMENT MARKER				
LOCATION				RAISED REFLECTIVE PAVEMENT MARKER EACH
<b>EASTBOUND I-80</b>				
STA	878+85.86	48.24 RT	TO 883+61.85 48.28 RT	12
STA	869+87.86	36.00 RT	TO 915+00.00 36.00 RT	12
STA	19+08.45	36.00 RT	TO 30+89.60 36.00 RT	12
<b>WESTBOUND I-80</b>				
STA	908+09.83	47.62 LT	TO 912+87.10 47.60 LT	12
STA	866+05.68	35.63 LT	TO 915+00.00 36.00 LT	61
STA	19+08.45	36.00 LT	TO 24+98.57 36.37 LT	7
<b>RAMP J</b>				
STA	299+51.61	CL	TO 307+10.09 CL	38
STA	302+51.18	16.00 LT	TO 307+10.09 16.00 LT	11
STA	317+74.87	4.00 LT	TO 319+10.93 4.00 LT	3
<b>RAMP K</b>				
STA	399+49.44	CL	TO 407+13.04 CL	38
STA	402+53.22	16.00 LT	TO 407+13.04 16.00 LT	11
STA	416+48.76	4.00 LT	TO 418+79.04 4.00 LT	6
<b>IL RTE 178</b>				
STA	96+00.00	6.50 RT	TO 106+58.69 5.75 RT	26
STA	96+00.00	6.50 LT	TO 104+73.91 9.50 LT	22
STA	107+40.74	21.75 RT	TO 109+55.53 23.00 RT	5
STA	111+43.88	9.00 LT	TO 113+83.58 9.00 LT	6
STA	116+23.73	9.00 RT	TO 118+85.58 9.00 RT	7
STA	120+52.08	23.00 LT	TO 122+67.08 23.00 LT	5
STA	123+47.91	23.00 RT	TO 125+62.91 23.00 RT	5
STA	123+63.61	9.00 RT	TO 125+62.91 9.00 RT	5
STA	131+69.75	6.57 RT	TO 134+52.15 CL	7
STA	131+69.75	1.5 LT	TO 134+52.15 CL	7
STA	134+52.15	CL	TO 139+57.18 CL	6
<b>TOTAL</b>				<b>327</b>

PAVEMENT MARKING FRONTAGE ROAD SCHEDULE 3								
LOCATION	PAINT PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	PAINT PAVEMENT MARKING TYPE I - LINE 4"	PAINT PAVEMENT MARKING TYPE I - LINE 12"	POLYUREA PAVEMENT MARKING TYPE I - LETTERS & SYMBOLS	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"
	(SQ FT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
STA 604+59.57 TO STA 621+56.37		8930.0						
STA 621+20	42							
STA 610+03 TO STA 621+00			565					
STA 621+86				15.6				
STA 621+56.37 TO IL RTE 178					501	93	65	42
<b>SUBTOTAL</b>				15.6	501	93	65	42
<b>TOTAL</b>	42	8930.0	565					

TEMPORARY PAVEMENT MARKING SCHEDULE	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 8"	TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL	WET TEMPORARY PAVEMENT MARKING TAPE TYPE III, 4"
	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)
TOTAL FROM PRESTAGE PHASES	731.3	8,516.8	1,783.3	0.0	0.0	3,998.2	8,373.6
TOTAL FROM STAGE 1 PHASES	3,464.2	21,469.2	3,703.7	0.0	183.7	16,454.4	84,334.3
TOTAL FROM STAGE 1 PHASES (ESTIMATED 2ND APP)	3,464.2	21,469.2	3,703.7	0.0	183.7	16,454.4	84,334.3
TOTAL FROM STAGE 2 PHASES	4,138.9	30,304.9	5,231.6	0.0	346.8	26,091.7	84,888.7
TOTAL FROM STAGE 3 PHASES	1,388.5	16,963.9	2,614.1	911.0	83.2	5,498.7	17,686.1
<b>TOTALS</b>	<b>13,187</b>	<b>98,724</b>	<b>17,037</b>	<b>911</b>	<b>797</b>	<b>68,497</b>	<b>279,617</b>

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center"><b>SCHEDULE OF QUANTITIES-11</b></p> <p>SCALE: VERT. N/A HORIZ. N/A</p> <p>DRAWN BY RDJ CHECKED BY</p>

© Copyright Hanson Professional Services Inc. 2009  
**HANSON**  
 Hanson Professional Services Inc.  
 1525 South Sixth Street  
 Springfield, Illinois 62703-2886  
 Offices Nationwide

MODEL NAME = Sheet 11  
 PLOT DATE = 12/23/2009  
 PLOT SCALE = 50.0000  
 USER NAME = Johna2009r44  
 LAYOUT: RDJ 01/20/06  
 DRAWN: RDJ 01/20/06  
 REVIEWED: MTM 10/1/07