

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	150-3HDK	LASALLE	492	41
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

EROSION CONTROL BLANKET DITCH LINING

LOCATION							EROSION CONTROL BLANKET
STA	TO	STA	SIDE	WIDTH			
				FS	W	BS	
RAMP I							
205+00	TO	212+00	RT	3	4	*	544.4
212+00	TO	226+53	RT	5	4	*	1453.0
212+00	TO	212+50	LT	1	4	1	33.3
RAMP J							
303+75	TO	305+29	RT	2	4	*	102.7
314+75	TO	316+75	RT	2	4	*	133.3
30950	TO	311+00	LT	1	4	*	83.3
RAMP K							
40037	TO	411+17	RT	4	4	*	960.0
411+17	TO	415+50	RT	6	4	*	481.1
IL 178**							
96+07	TO	97+43	RT	*	4	*	60.4
97+71	TO	98+51	RT	*	4	*	35.6
98+72	TO	100+15	RT	*	4	*	63.2
100+35	TO	101+38	RT	*	4	*	45.8
101+68	TO	102+81	RT	*	4	*	50.6
102+96	TO	103+58	RT	*	4	*	27.4
96+07	TO	97+43	LT	*	4	*	60.4
97+70	TO	101+20	LT	*	4	*	155.4
103+27	TO	103+65	LT	*	4	*	16.9
126+35	TO	127+38	RT	*	4	*	45.6
127+57	TO	129+49	RT	*	4	*	85.2
129+63	TO	134+00	RT	*	4	*	194.1
TOTAL							4,632

* 3:1 SLOPES QUANTIFIED WITH SEEDING
 ** EXTEND ECB 6' BEYOND END SECTION (2' UP ENT SIDE SLOPE) ON IL 178 ENTRANCES

TEMPORARY DITCH CHECKS

TEMP RAMP					FOOT
20+00.00	LT	TO	22+00.00	LT	200
19+20.00	RT	TO	21+25.00	RT	205
22+75.00	RT	TO	23+50.00	RT	75
TEMP RAMP K					
15+25.00	LT	TO	15+50.00	LT	25
15+00.00	RT	TO	15+50.00	RT	50
TEMP RAMP L					
12+00.00	RT	TO	13+50.00	RT	150
TEMP RAMP I					
11+45.00	RT	TO	12+65.00	RT	120
RTE 178					
98+90.00	LT	TO	100+00.00	LT	110
128+75.00	LT	TO	132+40.00	RT	365
134+30.00	LT	TO	136+30.00	RT	200
128+55.00	RT	TO	137+00.00	RT	845
TOTAL					2345

PERIMETER EROSION BARRIER

STA	OFFSET	SIDE	TO	STA	OFFSET	SIDE	LENGTH (FT)
IL RTE 178							
103+00.00	58.00	RT	TO	103+54.65	58.00	RT	54.7
103+78.08	59.68	RT	TO	105+50.00	61.85	RT	173.2
105+50.00	61.85	RT	TO	107+93.23	95.00	RT	245.4
107+93.23	95.00	RT	TO	108+53.36	135.53	RT	72.4
104+00.00	68.67	LT	TO	107+00.00	69.49	LT	299.5
107+00.00	69.49	LT	TO	107+84.00	82.37	LT	84.5
107+84.00	82.37	LT	TO	108+46.32	120.83	LT	74.1
318+50.00	97.44	RT	TO	121+57.46	126.36	RT	120.3
121+57.46	126.36	RT	TO	122+36.42	75.00	RT	97.7
122+36.42	75.00	RT	TO	124+59.76	64.67	RT	220.6
RAMP J							
316+50.00	97.44	RT	TO	318+50.00	97.44	LT	200.0
RAMP L							
507+50.00	50.41	RT	TO	508+86.39	24.70	RT	138.9
508+86.39	24.70	RT	TO	512+24.76	32.21	RT	338.4
512+24.76	32.21	RT	TO	512+50.32	40.37	RT	26.1
FRONTAGE ROAD							
604+50.00	40.00	LT	TO	610+00.00	40.00	LT	550.0
619+00.00	40.00	LT	TO	621+56.37	40.00	LT	256.4
604+50.00	40.00	RT	TO	608+00.00	40.00	RT	350.0
TOTAL							3,302

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

EROSION CONTROL SCHEDULE OF QUANTITIES

SCALE: VERT. N/A
 HORIZ. N/A
 DATE: _____ DRAWN BY KET
 CHECKED BY _____



MODEL NAME = Sheet 1
 PLOT DATE = 12/23/07
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = John@809144

LAYOUT	KET	12/05/07
DRAWN	KET	12/05/07
REVIEWED	MTM	10/1/07