

| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---------------------|-----------|---------------------------|--------------|-----------|
| 80 | 150-31HBK | LASALLE | 492 | 232 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |

BILL OF MATERIALS

INDEX OF SHEETS

| SHEET NO. | DESCRIPTION |
|-----------|--|
| 1 | INDEX OF SHEETS AND TOTAL BILL OF MATERIALS |
| 2-3 | BILL OF MATERIALS REMOVALS |
| 4 | BILL OF MATERIALS-REGULATORY AND WARNING SIGNS |
| 5 | BILL OF MATERIALS-GROUND MOUNTED SIGNS & RELOCATED SIGNS |
| 6 | BILL OF MATERIALS-OVERHEAD SIGNS |
| 7 | SIGN REMOVAL PLAN |
| 8-9 | SIGNING PLAN |
| 10-15 | SIGN PANEL DETAILS |
| 16-25 | OVERHEAD SIGN STRUCTURE |

LIST OF ILLINOIS DOT HIGHWAY STANDARDS

| STD. NUMBER | DESCRIPTION |
|-------------|---|
| 720001 | SIGN PANEL MOUNTING DETAILS |
| 720006 | SIGN PANEL ERECTION DETAILS |
| 720011 | METAL POSTS FOR SIGNS, MARKERS & DELINEATORS |
| 720021-02 | SIGN PANELS EXTRUDED ALUMINUM TYPE |
| 729001 | APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS) |

| DESCRIPTION | UNIT | TOTAL QUANTITY | REMOVALS | REGULATORY AND WARNING SIGNS | GROUND MOUNTED SIGNS | RELOCATED SIGNS | OVERHEAD SIGNS |
|---|-------|----------------|----------|------------------------------|----------------------|-----------------|----------------|
| SIGN PANEL - TYPE 1 | SQ FT | 153.71 | 0 | 153.71 | 0 | 0 | 0 |
| SIGN PANEL - TYPE 2 | SQ FT | 238.00 | 0 | 238.00 | 0 | 0 | 0 |
| SIGN PANEL - TYPE 3 | SQ FT | 2,839.75 | 0 | 60.00 | 2,367.25 | 0 | 412.50 |
| REMOVE SIGN PANEL ASSEMBLY-TYPE A | EACH | 8.00 | 4.00 | 0 | 0 | 4.00 | 0 |
| REMOVE SIGN PANEL ASSEMBLY-TYPE B | EACH | 13.00 | 9.00 | 0 | 0 | 4.00 | 0 |
| REMOVE SIGN PANEL-TYPE 1 | SQ FT | 199.70 | 190.51 | 0 | 0 | 9.19 | 0 |
| REMOVE SIGN PANEL-TYPE 2 | SQ FT | 125.00 | 79.00 | 0 | 0 | 46.00 | 0 |
| REMOVE SIGN PANEL-TYPE 3 | SQ FT | 1,634.00 | 1,606.00 | 0 | 0 | 28 | 0 |
| RELOCATE SIGN PANEL ASSEMBLY - TYPE A | EACH | 4.00 | 0 | 0 | 0 | 4.00 | 0 |
| RELOCATE SIGN PANEL ASSEMBLY - TYPE B | EACH | 4.00 | 0 | 0 | 0 | 4.00 | 0 |
| RELOCATE SIGN PANEL - TYPE 1 | SQ FT | 9.19 | 0 | 0 | 0 | 9.19 | 0 |
| RELOCATE SIGN PANEL - TYPE 2 | SQ FT | 46.00 | 0 | 0 | 0 | 46.00 | 0 |
| RELOCATE SIGN PANEL - TYPE 3 | SQ FT | 28.00 | 0 | 0 | 0 | 28.00 | 0 |
| MILE POST MARKER ASSEMBLY | EACH | 2.00 | 0 | 2.00 | 0 | 0 | 0 |
| STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY | POUND | 21,479.34 | 0 | 0.00 | 21,479.34 | 0.00 | 0 |
| WOOD SIGN SUPPORT | FOOT | 1,070.78 | 0 | 764.50 | 0.00 | 306.28 | 0 |
| OVERHEAD SIGN STRUCTURE - SPAN, TYPE 1A (4'-0" X 4'-6") | FOOT | 80.00 | 0 | 0 | 0 | 0 | 80.00 |
| OVERHEAD SIGN STRUCTURE WALKWAY | FOOT | 32.00 | 0 | 0 | 0 | 0 | 32.00 |
| CONCRETE FOUNDATIONS | CU YD | 39.46 | 0 | 0.00 | 39.46 | 0.00 | 0 |
| DRILLED SHAFT CONCRETE FOUNDATIONS | CU YD | 12.60 | 0 | 0 | 0 | 0 | 12.60 |
| REMOVE OVERHEAD SIGN STRUCTURE-SPAN | EACH | 1.00 | 1.00 | 0 | 0 | 0 | 0 |
| REMOVE GROUND-MOUNTED SIGN SUPPORT | EACH | 74.00 | 74.00 | 0 | 0 | 0 | 0 |
| REMOVE CONCRETE FOUNDATION-GROUND MOUNT | EACH | 26.00 | 26.00 | 0 | 0 | 0 | 0 |
| REMOVE CONCRETE FOUNDATION-OVERHEAD | EACH | 2.00 | 2.00 | 0 | 0 | 0 | 0 |
| STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE-SPAN | EACH | 2.00 | 0 | 0 | 0 | 0 | 2 |
| REINFORCEMENT BARS | POUND | 3,030.00 | 0 | 0.00 | 3,030.00 | 0.00 | 0 |

| REVISIONS | |
|-----------|----------|
| NAME | DATE |
| MOC, MLT | 11/25/08 |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
INDEX OF SHEETS AND
TOTAL BILL OF MATERIALS

SCALE: VERT.
HORIZ. N.T.S.
DATE

DRAWN BY MOC
CHECKED BY MLT



MODEL NAME = I:INDEX
PLOT DATE = 12/23/2009
PLOT SCALE = 1:300
USER NAME = John-602344

| | | |
|----------|-----|----------|
| LAYOUT | MOC | 02/08/05 |
| DRAWN | MOC | 02/08/05 |
| REVIEWED | MLT | 10/1/07 |