

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
BO	150-3HKB	LASALLE	492	234
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BILL OF MATERIALS - REMOVALS

SIGN REMOVAL NUMBER	ALIGNMENT NAME	STATION	LOCATION (LEFT, RIGHT, MEDIAN)	PANEL WIDTH FEET	PANEL HEIGHT FEET	SIGN AREA SQ. FT.	POST MATERIAL	REMOVE SIGN PANEL ASSEMBLY TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY TYPE B EACH	REMOVE SIGN PANEL TYPE 1 SQ. FT.	REMOVE SIGN PANEL TYPE 2 SQ. FT.	REMOVE SIGN PANEL TYPE 3 SQ. FT.	REMOVE OVERHEAD SIGN STRUCTURE SPAN EACH	REMOVE GROUND MOUNTED SIGN SUPPORT EACH	REMOVE CONCRETE FOUNDATION GROUND MOUNT EACH	REMOVE CONCRETE FOUNDATION OVERHEAD EACH	REMARKS
037	RAMP K	416+87	LEFT	3.00	3.00	9.00	WOOD		1					1			
				3.00	1.00	3.00											
				3.00	1.00	3.00											
				2.00	1.50	3.00											
038	RAMP K	416+91	RIGHT	3.00	3.00	9.00	WOOD			9.00				1			
039	RAMP L	501+28	RIGHT	4.00	5.00	20.00	WOOD		1					1			
				2.00	2.50	5.00											
044	IL 178	100+86	RIGHT	2.00	1.00	2.00	WOOD		1					1			
				3.00	3.00	9.00											
045	IL 178	106+40	LEFT	3.00	3.00	9.00	WOOD			9.00				1			
046	IL 178	107+56	RIGHT	14.00	18.00	252.00	STEEL					252.00		2	2		
047	IL 178	107+69	LEFT	3.00	3.00	9.00	WOOD			9.00				1			
048	IL 178	108+00	LEFT	2.00	1.00	2.00	WOOD	1						1			
				2.00	2.00	4.00											
049	IL 178	109+99	RIGHT	2.50	3.00	7.50	WOOD			7.50				1			
050	IL 178	110+43	LEFT	10.00	10.00	100.00	STEEL					100.00		2	2		
051	IL 178	111+98	LEFT	3.00	3.00	9.00	WOOD			9.00				1			
				2.00	1.00	2.00											
053	IL 178	116+91	LEFT	2.50	3.00	7.50	WOOD		1					1			
				2.50	1.50	3.75											
054	IL 178	119+57	RIGHT	11.00	11.00	121.00	STEEL					121.00		2	2		
055	IL 178	120+01	LEFT	1.00	1.75	1.75	WOOD	1						1			
				2.00	2.50	5.00											
056	IL 178	121+17	LEFT	14.00	18.00	252.00	STEEL					252.00		2	2		
057	IL 178	121+59	RIGHT	3.00	3.00	9.00	WOOD			9.00				1			
058	IL 178	122+20	MEDIAN	0.00	0.00	0.00	STEEL							1			MISSING SIGN PANEL
059	IL 178	123+00	RIGHT	2.00	1.00	2.00	STEEL	1						1			
				2.50	2.00	5.00											
060	IL 178	124+62	RIGHT	3.00	3.00	9.00	WOOD			9.00				1			
				2.00	1.00	2.00											
062	IL 178	132+40	LEFT	2.50	3.00	7.50	WOOD		1					1			
				3.00	3.00	9.00											
063	IL 178	135+02	LEFT	3.00	3.00	9.00	WOOD			9.00				1			
064	FRONTAGE RD.	620+31	RIGHT	2.00	0.50	1.00	WOOD	1						1			
				2.00	0.50	1.00											
065	FRONTAGE RD.	620+21	RIGHT	2.00	0.50	1.00	WOOD			9.00				1			
				3.00	3.00	9.00											
SUBTOTAL								4	5	79.50	0	725.00	0	27	8	0	

© Copyright Hanson Professional Services Inc. 2009
HANSON
 Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Offices Nationwide

MODEL NAME = 3 Removal.2
 PLOT DATE = 12/23/2009
 PLOT SCALE = 1:300
 USER NAME = jchm209344
 LAYOUT MOC 02/06/06
 DRAWN MOC 02/06/06
 REVIEWED MLT 10/1/07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
BILL OF MATERIALS
REMOVALS

SCALE: VERT.
HORIZ. N.T.S.
DATE

DRAWN BY MOC
CHECKED BY MLT