

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	150-318K	LASALLE	492	236
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BILL OF MATERIALS - GROUND MOUNTED SIGNS

SIGN PLAN SHEET NUMBER	ALIGNMENT NAME	STATION	LOCATION (LEFT RIGHT)	SIGN CODE	SIGN NUMBER	PANEL WIDTH FEET	PANEL HEIGHT FEET	POST ONE LENGTH LF	POST TWO LENGTH LF	WIDE FLANGE W6x15 LBS	WIDE FLANGE W8x18 LBS	WIDE FLANGE W10x22 LBS	WIDE FLANGE W14x30 LBS	WIDE FLANGE W14x38 LBS	WIDE FLANGE W16x45 LBS	CONC FND CY	REINFORCEMENT BARS LBS	SIGN PANEL TYPE 3 SF
8 OF 25	I-80 WB	19+80	RIGHT	GUIDE	10	10.50	15.50	30.58	32.28							3.80	226.00	162.75
8 OF 25	RAMP J	309+25	RIGHT	CAMPING	11	12.50	8.00	20.97	20.82		752.22					1.40	156.00	100.00
8 OF 25	RAMP J	311+25	RIGHT	LODGING	11A	12.50	8.00	21.06	22.93		791.82					1.40	156.00	100.00
8 OF 25	RAMP J	313+75	RIGHT	FOOD	12	12.50	8.00	20.74	22.61		780.30					1.40	156.00	100.00
8 OF 25	RAMP J	315+75	RIGHT	GUIDE	13	14.50	15.00	28.84	31.01					2,274.30		4.18	244.00	217.50
8 OF 25	RAMP J	317+75	RIGHT	GAS	14	12.50	8.00	20.83	22.71		783.72					1.40	156.00	100.00
8 OF 25	RAMP K	399+70	RIGHT	GUIDE	5	8.00	13.00	23.69	22.64		833.94					1.40	156.00	104.00
8 OF 25	RAMP K	408+50	RIGHT	CAMPING	6	12.50	8.00	20.97	18.55		711.36					1.40	156.00	100.00
8 OF 25	RAMP K	410+50	RIGHT	LODGING	6A	12.50	8.00	20.08	17.58	564.90						1.40	156.00	100.00
8 OF 25	RAMP K	413+50	RIGHT	FOOD	7	12.50	8.00	20.74	22.61		780.30					1.40	156.00	100.00
8 OF 25	RAMP K	415+50	RIGHT	GUIDE	8	14.50	12.50	25.84	28.01				1,615.50			3.80	226.00	181.25
8 OF 25	RAMP K	417+50	RIGHT	GAS	9	12.50	8.00	20.74	22.61		780.30					1.40	156.00	100.00
8 OF 25	IL 178	109+25	RIGHT	GUIDE	1	16.50	18.00	32.67	35.97						3,088.80	4.46	260.00	297.00
8 OF 25	IL 178	111+50	LEFT	GUIDE	2	10.50	10.50	23.47	25.67			1,081.08				2.36	184.00	110.25
8 OF 25	IL 178	118+80	RIGHT	GUIDE	3	14.50	13.00	26.20	29.10			1,659.00				3.80	226.00	188.50
8 OF 25	IL 178	120+50	LEFT	GUIDE	4	17.00	18.00	32.70	36.10						3,096.00	4.46	260.00	306.00
SUBTOTAL										564.90	6,213.96	1,081.08	5,160.30	2,274.30	6,184.80	39.46	3,030.00	2,367.25

BILL OF MATERIALS - RELOCATED SIGNS

SIGN PLAN SHEET NUMBER	ALIGNMENT NAME	STATION	LOCATION (LEFT RIGHT)	DESCRIPTION	PANEL WIDTH FEET	PANEL HEIGHT FEET	POST ONE LENGTH LF	POST TWO LENGTH LF	WOOD SIGN SUPPORT	REMOVE SIGN ASSEMBLY TYPE A EACH	REMOVE SIGN ASSEMBLY TYPE B EACH	REMOVE SIGN PANEL TYPE 1 SF	REMOVE SIGN PANEL TYPE 2 SF	REMOVE SIGN PANEL TYPE 3 SF	RELOCATE SIGN ASSEMBLY TYPE A EACH	RELOCATE SIGN ASSEMBLY TYPE B EACH	RELOCATE SIGN PANEL TYPE 1 SF	RELOCATE SIGN PANEL TYPE 2 SF	RELOCATE SIGN PANEL TYPE 3 SF	SIGN PANEL AREA SF
9 OF 25	IL 178	90+53	RIGHT	STOP ALL WAY	3.00	3.00	15.46		15.46		1.00					1.00				9.00
9 OF 25	IL 178	90+68	RIGHT	2 EACH BACK TO BACK, STREET NAME SIGNS	2.00	0.50	12.83		12.83	1.00					1.00					2.00
9 OF 25	IL 178	90+79	LEFT	STOP ALL WAY	3.00	3.00	15.64		15.64		1.00					1.00				9.00
9 OF 25	IL 178	90+79	LEFT	ILLINOIS 178 ARROW	1.50	0.75	15.60		15.60	1.00					1.00					4.00
9 OF 25	IL 178	90+79	LEFT	ROUTE 6 ARROW	2.00	2.00	16.35		16.35	1.00					1.00					4.00
9 OF 25	IL 178	92+45	LEFT	UTICA, OTTAWA, LA SALLE TOURIST INFORMATION I & M CANAL	5.00	4.00	19.31	20.06	39.37		1.00					1.00				20.00
9 OF 25	IL 178	92+45	RIGHT	INFO NORTH	2.00	1.00	15.10		15.10	1.00					1.00					2.00
9 OF 25	IL 178	92+45	RIGHT	ILLINOIS 178	2.00	2.00	13.90		13.90			4.00					4.00			4.00
9 OF 25	IL 178	94+50	LEFT	CRIME STOPPERS (ON LIGHT POLE) UTICA 1000	4.00	2.50	14.26	14.82	29.08				10.00					10.00		10.00
9 OF 25	IL 178	95+36	LEFT	STARVED ROCK, BUFFALO ROCK, MATTHIESSEN GRAND BEAR LODGE	7.00	4.00	19.04	20.09	39.13					28.00			3.00		28.00	28.00
9 OF 25	IL 178	96+55	RIGHT	ARROW	2.00	1.50						3.00					3.00			3.00
9 OF 25	IL 178	96+55	RIGHT	TRUCK	1.75	1.25						2.19					2.19			2.19
9 OF 25	IL 178	96+55	RIGHT	DIVIDED HIGHWAY	3.00	3.00	18.82		18.82				9.00					9.00		9.00
9 OF 25	IL 178	98+06	LEFT	JCT ROUTE 6	3.00	3.00	17.07		17.07				9.00					9.00		9.00
9 OF 25	IL 178	99+65	RIGHT	STOP AHEAD	2.50	1.25	19.15		19.15		1.00					1.00				3.13
9 OF 25	IL 178	99+65	RIGHT	STOP AHEAD	3.00	3.00	19.39		19.39				9.00					9.00		9.00
9 OF 25	IL 178	99+65	LEFT	STOP AHEAD	3.00	3.00	19.39		19.39				9.00					9.00		9.00
SUBTOTAL									306.28	4.00	4.00	9.19	46.00	28.00	4.00	4.00	9.19	46.00	28.00	0.00

REVISIONS	
NAME	DATE
MOC, MLT	11/25/08

ILLINOIS DEPARTMENT OF TRANSPORTATION
SIGNING PLAN
BILL OF MATERIALS
GROUND MOUNTED SIGNS
& RELOCATED SIGNS

SCALE: VERT.
HORIZ. N.T.S.
DATE

DRAWN BY MOC
CHECKED BY MLT



MODEL NAME = 5 GRND.MOUNT1	LAYOUT	MOC	02/08/06
PLOT DATE = 12/23/2009	DRAWN	MOC	02/08/06
PLOT SCALE = 1/32" = 1'-0"	REVIEWED	MLT	10/1/07
USER NAME = Johnna20944			