

SUMMARY OF QUANTITIES			100% STATE
CODE NO.	ITEM	CONSTRUCTION TYPE CODE	X-071-2A SN 050-0240
		UNIT	
20200100	EARTH EXCAVATION	CU YD	290
20400800	FURNISHED EXCAVATION	CU YD	1,040
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	126
25000210	SEEDING, CLASS 2A	ACRE	1.00
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90
25100115	MULCH, METHOD 2	ACRE	1.64
25100630	EROSION CONTROL BLANKET	SQ YD	1,862
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100
28000305	TEMPORARY DITCH CHECKS	FOOT	200
28000400	PERIMETER EROSION BARRIER	FOOT	2,065
28100107	STONE RIPRAP, CLASS A4	SQ YD	702
28200200	FILTER FABRIC	SQ YD	702
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	733
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	73.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	562
40600300	AGGREGATE (PRIME COAT)	TON	14.0
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.7
40600525	LEVELING BINDER (HAND METHOD), N50	TON	1.8
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	148.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	585
40600990	TEMPORARY RAMP	SQ YD	43.8
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	160.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	296.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	23
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	240
42001300	PROTECTIVE COAT	SQ YD	240
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	60
44000100	PAVEMENT REMOVAL	SQ YD	408
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	27
44004250	PAVED SHOULDER REMOVAL	SQ YD	220
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	210
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
X5018200	REMOVE EXISTING CULVERTS	EACH	(3)
50200100	STRUCTURE EXCAVATION	CU YD	330
50300100	FLOOR DRAINS	EACH	12
50300225	CONCRETE STRUCTURES	CU YD	89.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	153.5
50300260	BRIDGE DECK GROOVING	SQ YD	456
50300280	CONCRETE ENCASMENT	CU YD	6.6
50300300	PROTECTIVE COAT	SQ YD	553
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1

SUMMARY OF QUANTITIES			100% STATE
CODE NO.	ITEM	CONSTRUCTION TYPE CODE	X-071-2A SN 050-0240
		UNIT	
50500505	STUD SHEAR CONNECTORS	EACH	2,052
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	45,040
50800515	BAR SPLICERS	EACH	512
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	1,282
51202305	DRIVING PILES	FOOT	1,282
51203200	TEST PILE METAL SHELLS	EACH	2
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	48
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	122
54213450	END SECTIONS 15"	EACH	6
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	66
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	182
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, & FOOT POSTS	FOOT	450
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4
63200310	GUARDRAIL REMOVAL	FOOT	412
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	180
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,129
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	30
70400100	TEMPORARY CONCRETE BARRIER	FOOT	466
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	320
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,129
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	10
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	3
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16
78200520	BARRIER WALL MARKERS, TYPE B	EACH	8
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	11
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	319
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION- LOCATION 1	EACH	1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION- LOCATION 2	EACH	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2

\* SPECIALTY ITEMS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	(3)BR-1	LASALLE	44	3
STA. N/A		TO STA. N/A		
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				

**CONTRACT NO. 66619**

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<b>SUMMARY OF QUANTITIES</b>
		SCALE: NONE
		DATE: JUNE 20, 2008
		DRAWN BY SAS
		CHECKED BY AAG