

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1-80	50-8 HBR	LASALLE	143	4
STA.		TO STA.		
FED. ROAD DIST. NO. 3		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE	
				ROADWAY	BRIDGE
				I-000	X271-2A
60625800	ISLAND PAVEMENT (SPECIAL)	SQ YD	151	151	0
60900515	CONCRETE THRUST BLOCKS	EACH	4	4	0
61000225	TYPE F INLET BOX, STANDARD 610001	EACH	4	4	0
△ 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	700	700	0
△ 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	0
△ 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	0
63200310	GUARDRAIL REMOVAL	FOOT	2117	2117	0
66500105	WOVEN WIRE FENCE, 4'	FOOT	237	237	0
66502300	WOVEN WIRE FENCE REMOVAL	FOOT	234	234	0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	0
67100100	MOBILIZATION	L SUM	1.0	1.0	0.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0	0.0
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	1.0	0.0
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1.0	1.0	0.0
70103816	TRAFFIC CONTROL SURVEILLANCE	CAL MO	9	9	0
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	18	18	0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	292	292	0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6020	6020	0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	2519	2519	0
△ 70500200	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	525	525	0
△ 70500655	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2	0
△ 72000100	SIGN PANEL - TYPE 1	SQ FT	15.25	15.25	0.00
△ 72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	154.51	154.51	0.00
△ 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	990	990	0
△ 73000100	WOOD SIGN SUPPORT	FOOT	422.4	422.4	0.0
73400100	CONCRETE FOUNDATIONS	CU YD	2.8	2.8	0.0
△ 73502000	RELOCATE GROUND-MOUNTED SIGN SUPPORT	EACH	4	4	0
△ 73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4	4	0
△ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	62	62	0
△ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8473	8473	0
△ 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	853	853	0
△ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	912	912	0
△ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	134	134	0
△ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	14	14	0
△ 78200300	PRISMATIC CURB REFLECTOR	EACH	14	14	0

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE	
				ROADWAY	BRIDGE
				I-000	X271-2A
△ 78200420	GUARDRAIL MARKERS, TYPE B	EACH	120	120	0
△ 78200520	BARRIER WALL MARKERS, TYPE B	EACH	14	14	0
△ 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6	0
△ 78300100	PAVEMENT MARKING REMOVAL	SQ FT	5287	5287	0
△ 81800185	AERIAL CABLE, 2-1/C NO. 1/0 WITH MESSENGER WIRE	FOOT	1566	1566	0
△ 83000010	LIGHT POLE, ALUMINUM, 16 FT M.H., 6 FT DAVIT ARM	EACH	2	2	0
△ 83000015	LIGHT POLE, ALUMINUM, 16 FT M.H., 10 FT DAVIT ARM	EACH	2	2	0
△ 83000020	LIGHT POLE, ALUMINUM, 17 FT M.H., 10 FT DAVIT ARM	EACH	3	3	0
△ 83000025	LIGHT POLE, ALUMINUM, 18 FT M.H., 10 FT DAVIT ARM	EACH	4	4	0
△ 83000030	LIGHT POLE, ALUMINUM, 20 FT M.H., 6 FT DAVIT ARM	EACH	3	3	0
△ 83000035	LIGHT POLE, ALUMINUM, 20 FT M.H., 10 FT DAVIT ARM	EACH	3	3	0
△ 80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	0
△ 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	54	54	0
△ 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	454	454	0
△ 81104600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., INTERMEDIATE METAL	FOOT	240	240	0
△ 81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	12	12	0
△ 81603035	UNIT DUCT, 600V, 2-1/C NO.6, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2534	2534	0
△ 81603070	UNIT DUCT, 600V, 2-1/C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	2195	2195	0
△ 81603095	UNIT DUCT, 600V, 4-1/C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	875	875	0
△ 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	783	783	0
△ 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	256	256	0
△ 81702150	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 2	FOOT	2055	2055	0
△ 81800190	AERIAL CABLE, 2-1/C NO. 2 WITH MESSENGER WIRE	FOOT	827	827	0
△ 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5425	5425	0
△ 82102100	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 100 WATT	EACH	18	18	0
△ 82102150	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 150 WATT	EACH	9	9	0
△ 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	9	9	0
△ 82500350	LIGHTING CONTROLLER, BASE MOUNTED 240 VOLT, 100 AMP	EACH	1	1	0
△ 83001400	LIGHT POLE, ALUMINUM, 35 FT. M.H., 10 FT. DAVIT ARM	EACH	2	2	0
△ 83002400	LIGHT POLE, ALUMINUM, 40 FT. M.H., 10 FT. DAVIT ARM	EACH	4	4	0
△ 83057145	LIGHT POLE, WOOD, 30 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	10	10	0
△ 83057150	LIGHT POLE, WOOD, 30 FOOT, CLASS 4	EACH	4	4	0
△ 83057285	LIGHT POLE, WOOD, 50 FOOT, CLASS 3, WITH 15FT MAST ARM	EACH	3	3	0
△ 83057290	LIGHT POLE, WOOD, 50 FOOT, CLASS 4	EACH	4	4	0

△ SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 FAI ROUTE 80 UNDER FAU 6097 (PLANK ROAD)

**SUMMARY OF QUANTITIES**

SCALE: VERT. NONE  
 HORIZ. N.T.S.  
 DATE: 12/02/09

DRAWN BY: ENTRAN/CAD  
 CHECKED BY: TMH

PLOT DATE = 2/14/2010  
 FILE NAME = g:\projects\2005-1089\_001\cadd\PLANS\01-ds  
 PLOT SCALE = 60.00 / IN.  
 PLOT TIME = 4:00:00 PM

