

PAVEMENT MARKING SCHEDULE						
LOCATION	LENGTH	PAINT PVMT MARKING		PAINT PVMT MARKING	RAISED REFLECTIVE PVMT MARK	RAISED REFLECTIVE PVMT MARK REMOVAL
		WHITE 4"	YELLOW 4"	YELLOW 6"	EACH	EACH
		FOOT	FOOT	FOOT		
206+23.70 TO 213+00	676.3		1353		9	9
213+00 TO 221+00	800		800	200	11	11
221+00 TO 237+75	1675			419	22	22
237+75 TO 328+62.58	9087.58	18175	80	2272	115	115
SUBTOTAL		18175	2233	2891	157	157
TOTAL		20408		2891	157	157

* PROPOSED NO PASSING ZONES SHALL BE STRIPED AS EXISTING.

TEMPORARY PAVEMENT MARKING SCHEDULE				
LOCATION	LENGTH	TEMPORARY PVMT MARKING		TEMPORARY PVMT MARKING
		WHITE 4"	YELLOW 4"	YELLOW 6"
		FOOT	FOOT	FOOT
206+23.70 TO 213+00	676.3		1353	
213+00 TO 221+00	800		800	200
221+00 TO 237+75	1675			419
237+75 TO 328+62.58	9087.58	18175	80	2272
SUBTOTAL		18175	2233	2891
TOTAL		20408		2891

SHORT TERM MARKING SCHEDULE			
LOCATION	LENGTH	SHORT-TERM PAVEMENT MARKING	WORK ZONE PVMT MARKING REMOVAL
		YELLOW	SQ FT
		FOOT	
206+23.70 TO 213+00	676.3	203	23
213+00 TO 221+00	800	240	27
221+00 TO 237+75	1675	503	56
237+75 TO 328+62.58	9087.58	2726	303
TOTAL		3672	409

SEEDING SCHEDULE								
LOCATION	SIDE	SEEDING CL 2	FURN EXC	EROSION CONTROL BLANKET	NIT FERT NUT	PHOS FERT NUT	POT FERT NUT	
		ACRE	CU YD	SQ YD	LB	LB	LB	
FIRST ST.	238+60	LT	0.01	1.5	52	0.9	0.9	0.9
EAST 275TH ROAD	263+10.5	LT	0.01	1.5	52	0.9	0.9	0.9
EAST 275TH ROAD	263+10.5	RT	0.01	1.5	52	0.9	0.9	0.9
EAST 350TH ROAD	303+44.5	RT	0.01	1.5	52	0.9	0.9	0.9
EAST 350TH ROAD	303+44.6	RT	0.01	1.5	52	0.9	0.9	0.9
TOTAL			0.05	7.5	260	4.5	4.5	4.5