

**MAINLINE SCHEDULE**

STATION TO STATION	AREA	HMA SURF REM 1"	HMA SURF REM 3 1/2"	HMA SURF REM 5"	HMA SURF REM BUTT JT	CONC PVT SCARIF	PAVED SHLDR REM	POLY BIT MATLS PR CT	P HMA BC IL-19.0 N105	P HMA SURF CSE MIX "E" N105	HMA SURF CSE MIX "C" N50	HMA SHLDR 10"	INC HMA	TEMP RAMP	PAVT MKING TAPE, TY III (SPECIAL)	AGG SHLDS TY B
		SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	GALLON	TON	TON	TON	SQ YD	TON	SQ YD	FOOT
<b>LASALLE COUNTY</b>																
810+00 TO 866+79.61	48,694	11360		31,554	214		5782	8278	7775	4265	1414	7788		214	2954	984
866+79.61 TO 885+07	15,667	3655		10,153	214		1860	2665	2502	1373	455	2506		214	951	317
885+07 TO 937+90	45,293	10,566		29,350	214		5378	7700	7232	3967	1315	7244		214	2748	915
937+90 TO 990+89	45,431	10,598		29,439	214		5394	7723	7254	3980	1319	7266		214	2756	918
990+89 TO 1049+98.56	50,665	11,820		32,831	214		6016	8613	8090	4438	1471	8104		214	3074	1024
1049+98.56 TO 1096+98	40,290	9399		26,108	214		4784	6849	6434	3529	1170	6444		214	2444	814
1096+98 TO 1149+98.56	45,444	10,602		29,448	214		5396	7726	7256	3981	1320	7268		214	2758	918
924+91 MAINT CROSSOVER	165	165						17					19			6
1073+35 MAINT CROSSOVER	148	148						15					17			6
<b>SUBTOTALS</b>		68,313	0	188,883	1498	0	34,610	49,586	46,543	25,533	8464	46,620	36	1498	17,685	5902
<b>GRUNDY COUNTY</b>																
1149+98.56 TO 1155+51.2	4738	1106		3071	214		564	807	757	415	138	758		214	289	96
724+16 TO 766+60	36,386	8488		23,578	214		4320	6186	5810	3187	1057	5820		214	2208	735
766+60 TO 790+50	20,491	4,780		13,278	214		2434	3484	3272	1795	595	3278		214	1243	414
790+50 TO 819+51	4,612	16,117		107	1222		4054	4342	3972	2179	723	3978		224	1510	803
819+51 TO 846+97	23,543	4,303	15,256		214	1157	3896	4110	3759	2062	684	3766		331	1429	776
786+34 MAINT CROSSOVER	149	149						15					17			6
1095+30 LOCKED GATE ACCESS EB	360	290			70			36					40			6
1101+23 LOCKED GATE ACCESS WB	360	290			70			36					40			6
<b>SUBTOTALS</b>		24,018	31,373	39,927	1103	2379	15,268	19,016	17,570	9638	3197	17,600	97	1197	6679	2842
<b>TOTALS</b>		92,331	31,373	228,810	2601	2379	49,878	68,602	64,113	35,171	11,661	64,220	133	2695	24,364	8744

\* STA 1155+51.20 BK = STA 724+16 AH  
6" HMA SHOULDER IS INCLUDED ON SEEDING / STABILIZATION SCHEDULE

**PAVEMENT MARKING**

STATION TO STATION	GROOVING REC PVT MRKING 5"	GROOVING REC PVT MRKING 9"	WET REFLEC PREFORM PLASTIC PVT MRKING LINE 6"	WET REFLECTIVE THERMOPLASTIC PAVEMENT MRKING				TEMP PVT MRKING			RAISED REF PVT MRKS EACH		
				4"		8"	12"	4"		6"		8"	12"
				WHITE	YELLOW	WHITE	WHITE	WHITE	YELLOW	WHITE		WHITE	WHITE
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
<b>LASALLE COUNTY</b>													
810+00 TO 866+79.61	22718	2820	2840	11359	11359	2820		11359	11359	2840	2820		355
866+79.61 TO 885+07	7310		914	3655	3655			3655	3655	914			91
885+07 TO 937+90	21,132		2642	10,566	10,566			10,566	10,566	2642			264
937+90 TO 990+89	21,196		2650	10,598	10,598			10,598	10,598	2650			265
990+89 TO 1049+98.56	23,638		2955	11,819	11,819			11,819	11,819	2955			295
1049+98.56 TO 1096+98	18,798		2350	9399	9399			9399	9399	2350			235
1096+98 TO 1149+98.56	21,202		2650	10,601	10,601			10,601	10,601	2650			265
<b>SUBTOTALS</b>	135,994	2820	16,999	67,997	67,997	2820	0	67,997	67,997	16,999	2820	0	1771
<b>GRUNDY COUNTY</b>													
1149+98.56 TO 1155+51.2	2211		276	1105	1105			1105	1105	276			28
724+16 TO 766+60	16,976		2122	8488	8488			8488	8488	2122			212
766+60 TO 819+51	21,164		2646	10,582	10,582			10,582	10,582	2646			265
819+51 TO 846+97	10,984	2670	1373	5492	5492	2670	1014	5492	5492	1373	2670	1014	204
<b>SUBTOTALS</b>	51,335	2670	6417	25,667	25,667	2670	1014	25,667	25,667	6417	2670	1014	709
<b>TOTALS</b>	187,329	5490	23,416	93,664	93,664	5490	1014	93,664	93,664	23,416	5490	1014	2480

\* STA 1155+51.20 BK = STA 724+16 AH