TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	HMA SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL 0.75 IN	POLYMERIZED Bituminous MATERIALS PRI. COAT	AGGREGATE MATERIALS PRIME COAT	POLYMERIZED LEV. BNDR. (MM) IL. 4.75 N50	HMA SURF CSE MIX "D" N50 1.50 IN	HOT-MIX ASPHALT SURFACE COURSE MIX C, N50, SHOULDERS				AGGREGATE SHOULDERS TYPE B, WEDGE			
											LEFT AREA	LEFT SIDE	RIGHT AREA	RIGHT SIDE	LEFT AREA	LEFT SIDE	RIGHT AREA	RIGHT SIDE
	FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	SQ YD	TON	SQ YD	TON	SQ YD	TON	SQ YD	TON
STA. 270 + 24 TO 271 + 32	24.00	108.00	288.00	80.00	13.33	288.00	0.16	0.94	12.13	24.32	36.00	4.14			30.00	5.64	30.00	5.64
STA. 271 + 32 TO 279 + 18	24.00	786.00	2096.00			2096.00	1.09	6.29	88.26	184.93					218.33	41.03	218.33	41.03
STA. 279 + 18 TO 286 + 32	24.00	714.00	1904.00			1904.00	0.99	5.71	80.18	175.21					198.33	37.27	198.33	37.27
STA. 286 + 32 TO 290 + 04	24.00	372.00	992.00			992.00	0.52	2.98	41.77	87.52					103.33	19.42	103.33	19.42
STA. 290 + 04 TO 297 + 34	24.00	730.00	1946.67			1946.67	1.01	5.84	81.97	179.13					202.78	38.11	202.78	38.11
STA. 297 + 34 TO 297 + 82	24.00	48.00	128.00			128.00	0.07	0.38	5.39	11.78					13.33	2.51	13.33	2.51
STA. 297 + 82 TO 299 + 16	24.00	134.00	357.33			357.33	0.19	1.07	15.05	32.88					37.22	6.99	37.22	6.99
STA. 299 + 16 TO 299 + 42	24.00	26.00	69.33			69.33	0.04	0.21	2.92	6.38					7.22	1.36	7.22	1.36
STA. 299 + 42 TO 301 + 04	24.00	162.00	432.00			432.00	0.22	1.30	18.19	39.75					45.00	8.46	45.00	8.46
STA. 301 + 04 TO 302 + 18	24.00	114.00	304.00			304.00	0.16	0.91	12.80	25.67					31.67	5.95	31.67	5.95
STA. 302 + 18 TO 311 + 14	24.00	896.00	2389.33			2389.33	1.24	7.17	100.61	201.75					248.89	46.77	248.89	46.77
STA. 311 + 14 TO 314 + 00	24.00	286.00	762.67			762.67	0.43	2.48	32.12	67.29	95.33	10.97			79.44	14.93	79.44	14.93
STA. 314 + 00 TO 315 + 32	24.00	132.00	352.00			352.00	0.18	1.06	14.82	29.72					36.67	6.89	36.67	6.89
STA. 315 + 32 TO 317 + 42	24.00	210.00	560.00			560.00	0.35	1.96	23.58	51.53	70.00	8.06	70.00	8.06	58.33	10.96	58.33	10.96
STA. 317 + 42 TO 318 + 90	24.00	148.00	394.67			394.67	0.21	1.18	16.62	33.32					41.11	7.73	41.11	7.73
STA. 318 + 90 TO 320 + 07	24.00	117.00	312.00			312.00	0.16	0.94	13.14	26.34					32.50	6.11	32.50	6.11
STA. 320 + 07 TO 322 + 23	24.00	216.00	576.00			576.00	0.30	1.73	24.26	48.64					60.00	11.28	60.00	11.28
STA. 322 + 23 TO 330 + 87	24.00	864.00	2304.00			2304.00	1.20	6.91	97.02	194.54					240.00	45.10	240.00	45.10
STA. 330 + 87 TO 331 + 05	24.00	18.00	48.00			48.00	0.03	0.16	2.02	4.24	8.00	0.91			5.00	0.94	5.00	0.94
STA. 331 + 05 TO 334 + 13	24.00	308.00	821.33			821.33	0.63	3.49	34.59	75.58	205.33	23.32	308.00	34.82	85.56	16.08	85.56	16.08
STA. 333 + 83 TO 334 + 13	24.00	30.00	80.00	140.00	23.33	80.00	0.07	0.36	3.37	7.36	30.00	3.39	30.00	3.39				
GAP STRUCTURE 072-0118																		
STA. 336 + 83 TO 337 + 13	24.00	30.00	80.00	140.00	23.33	80.00	0.07	0.36	3.37	7.36	30.00	3.39	30.00	3.39				
STA. 337 + 13 TO 338 + 29	24.00	116.00	309.33			309.33	0.25	1.39	13.03	28.47	116.00	13.11	116.00	13.11	32.22	6.06	32.22	6.06
STA. 338 + 29 TO 339 + 11	24.00	82.00	218.67			218.67	0.17	0.93	9.21	20.12	54.67	6.21	82.00	9.27	22.78	4.28	22.78	4.28
STA. 339 + 11 TO 340 + 19	24.00	108.00	288.00			288.00	0.20	1.13	12.13	26.50	60.00	6.83	72.00	8.18	30.00	5.64	30.00	5.64
STA. 340 + 19 TO 351 + 88	24.00	1169.00	3117.33			3117.33	1.62	9.35	131.27	263.22					324.72	61.02	324.72	61.02
STA. 351 + 88 TO 360 + 43	24.00	855.00	2280.00			2280.00	1.19	6.84	96.01	192.52					237.50	44.63	237.50	44.63
STA. 360 + 43 TO 361 + 67	24.00	124.00	330.67			330.67	0.17	0.99	13.92	27.92					34.44	6.47	34.44	6.47
STA. 361 + 67 TO 367 + 95	32.00	628.00	2232.89			2232.89	1.16	6.70	93.96	207.34					174.44	32.78	174.44	32.78
STA. 367 + 95 TO 373 + 91	28.00	596.00	1854.22			1854.22	0.96	5.56	78.05	162.48					165.56	31.11	165.56	31.11
STA. 373 + 91 TO 378 + 60	24.00	469.00	1250.67			1250.67	0.65	3.75	52.66	105.60					130.28	24.48	130.28	24.48
STA. 378 + 60 TO 380 + 07	29.00	147.00	473.67			473.67	0.25	1.42	19.94	39.96					40.83	7.67	40.83	7.67
STA. 380 + 07 TO 383 + 18	36.00	311.00	1244.00			1244.00	0.65	3.73	52.34	104.86					86.39	16.23	86.39	16.23
STA. 383 + 18 TO 388 + 20	38.00	502.00	2119.56	126.67	21.11	2119.56	1.10	6.36	89.17	178.63					139.44	26.20	139.44	26.20
STA. 388 + 20 TO 388 + 90	34.00	70.00	264.44			264.44	0.14	0.79	11.13	22.30					19.44	3.65	19.44	3.65
STA. 388 + 90 TO 390 + 64	31.00	174.00	599.33			599.33	0.31	1.80	25.22	50.55					48.33	9.08	48.33	9.08
STA. 390 + 64 TO 392 + 50	25.00	186.00	516.67			516.67	0.28	1.59	21.75	43.62	20.67	2.51			51.67	9.71	51.67	9.71
STA. 392 + 50 TO 401 + 36	25.00	886.00	2461.11			2461.11	1.28	7.38	103.63	207.77					246.11	46.25	246.11	46.25
STA. 401 + 36 TO 404 + 42	24.00	306.00	816.00			816.00	0.51	2.86	34.36	75.09	102.00	11.74	102.00	11.74	85.00	15.97	85.00	15.97
STA. 404 + 42 TO 406 + 25	24.00	183.00	488.00			488.00	0.34	1.91	20.55	44.91	61.00	7.02	162.67	18.41	50.83	9.55	50.83	9.55
STA. 406 + 25 TO 411 + 25	24.00	500.00	1333.33			1333.33	0.69	4.00	56.15	112.58					138.89	26.10	138.89	26.10
STA. 411 + 25 TO 412 + 35	24.00	110.00	293.33			293.33	0.17	0.95	12.35	26.99	12.22	1.48	24.44	2.85	30.56	5.74	30.56	5.74
STA. 412 + 25 TO 417 + 28	24.00	503.00	1341.33			1341.33	0.70	4.02	56.48	113.26					139.72	26.26	139.72	26.26
STA. 417 + 28 TO 418 + 84	24.00	156.00	416.00			416.00	0.22	1.25	17.52	35.13					43.33	8.14	43.33	8.14
STA. 418 + 84 TO 420 + 67	24.00	183.00	488.00			488.00	0.27	1.55	20.55	41.21	20.33	2.47	20.33	2.47	50.83	9.55	50.83	9.55
STA. 420 + 67 TO 424 + 00	24.00	333.00	888.00			888.00	0.48	2.74	37.39	74.98	37.00	4.49			92.50	17.38	92.50	17.38
STA. 424 + 00 TO 493 + 95	24.00	6995.00	18653.33			18653.33	9.70	55.96	785.48	1575.04					1943.06	365.13	1943.06	365.13
STA. 493 + 95 TO 497 + 20	24.00	325.00	866.67			866.67	0.57	3.18	36.49	76.47			288.89	32.69	90.28	16.96	90.28	16.96
STA. 497 + 20 TO 499 + 69	24.00	249.00	664.00			664.00	0.35	1.99	27.96	56.07					69.17	13.00	69.17	13.00
STA. 499 + 69 TO 500 + 29	24.00	60.00	160.00			160.00	0.09	0.53	6.74	14.72	13.33	1.56	13.33	1.56	16.67	3.13	16.67	3.13
STA. 500 + 29 TO 501 + 19	24.00	90.00	240.00			240.00	0.15	0.83	10.11	22.09	20.00	2.33	35.00	4.01	25.00	4.70	25.00	4.70
STA. 501 + 19 TO 502 + 44	24.00	125.00	333.33			333.33	0.23	1.28	14.04	30.67	27.78	3.24	111.11	12.57	34.72	6.52	34.72	6.52
STA. 502 + 44 TO 503 + 19	24.00	75.00	200.00			200.00	0.12	0.69	8.42	18.40	16.67	1.94	29.17	3.34	20.83	3.91	20.83	3.91
STA. 503 + 19 TO 507 + 00	24.00	381.00	1016.00			1016.00	0.73	4.06	42.78	93.49	84.67	9.88	423.33	47.81	105.83	19.89	105.83	19.89
STA. 507 + 00 TO 508 + 47	24.00	147.00	392.00			392.00	0.26	1.44	16.51	36.07	39.78	4.64	93.50	10.67	40.83	7.67	40.83	7.67
STA. 508 + 47 TO 508 + 77	238.00	30.00	793.33			793.33	0.42	2.43	33.33	67.28	6.67	0.78	20.00	2.27	8.33	1.57	8.33	1.57
STA. 270 + 24 TO 508 + 77	24.00	23852.79	63607.44															
GRAND-TOTAL				**487**	**81**	**66,141**	**35.7**	**204.8**	**2,785**	**5,712**	**1,167**	134	2,032	231	6,545	1,230	6,545	1,230
												TOTAL	**3199.22**	**365.03**		**TOTAL**	**13091**	**2460**

FARMINGTON RD. 3P-from KICKAPOO CRK. to IL.116

S:\GEN\DRAFT\STDPLNS\SQUAD14-F-Contracts\68502 Farmington Rd.dgn
S:\GEN\DRAFT\STDPLNS\SQUAD14-F-Contracts\68502 Farmington Rd.dgn

FILE NAME = 68502 Farmington Rd.dgn	USER NAME = jonesce	DESIGNED - CEJ	REVISED - ___	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TABULATION OF RESURFACING QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN - CEJ	REVISED - ___			6659	11RS-3	PEORIA	40 / 10
	PLOT SCALE = 103.7051 ' / IN.	CHECKED - ENE	REVISED - ___			PPP		CONTRACT NO. 68502	
	PLOT DATE = 1/25/2010	DATE - 01/15/2010	REVISED - ___		SCALE: _____ SHEET NO. __ OF ___ SHEETS STA. _____ TO STA. _____	FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT	