

HOT-MIX ASPHALT SURFACE REMOVAL BUTT-JOINT				TEMPORARY RAMP		
LOCATION	40600982			40600990		
	Width	Length	SQYD	Width	Length	SQYD
Sta. 270+64.70 MAINLINE	24	30	80	24	5	13.3
Sta. 270+64.70 N. KICKAPOO CRK. RD.	25	18	50	25	5	13.9
Sta. 270+55.31 S. KICKAPOO CRK. RD.	25	18	50	25	5	13.9
Sta. 272+08 E. REDBUD DR.	20	12	26.7	20	5	11.1
Sta. 302+18 N. HILLTOP RD.	20	12	26.7	20	5	11.1
Sta. 306+40 OAKLEAF RD.	22	12	29.3	22	5	12.2
Sta. 311+14 SUNSET DR.	20	12	26.7	20	5	11.1
Sta. 317+48 W. REDBUD DR.	28	18	56	28	5	15.6
Sta. 317+48 FERNWOOD CIRCLE	28	12	37.3	28	5	15.6
Sta. 322+23 LIMESTONE LN.	28	12	37.3	28	5	15.6
Sta. 332+20 ANDERSON LN.	22	12	29.3	22	5	12.2
Sta. 270+64.70 MAINLINE	42	30	140	42	5	23.3
Sta. 334+13 -336+83 BRIDGE OMISSION						
Sta. 270+64.70 MAINLINE	42	30	140	42	5	23.3
Sta. 338+29 HIGHLAND DR.	15	12	20	15	5	8.3
Sta. 340+47 TRADEWIND DR.	30	12	40	30	5	16.7
Sta. 341+74 COUNTRY LN.	22	12	29.3	22	5	12.2
Sta. 343+90 TOWER RD.	26	18	52	26	5	14.4
Sta. 348+32 TIMBERLAKE LN.	22	12	29.3	22	5	12.2
Sta. 351+30 RANGE RD.	20	12	26.7	20	5	11.1
Sta. 356+95 SHELTON LN.	18	12	24	18	5	10
Sta. 367+95 DEMPSTER LN.	20	12	26.7	20	5	11.1
Sta. 373+70 FARM. RD. STORAGE	20	12	26.7	20	5	11.1
Sta. 376+72 WILDWOOD CT.	20	12	26.7	20	5	11.1
Sta. 380+07 CHERRY ST.	20	12	26.7	20	5	11.1
Sta. 383+18 WOODS RD.	20	12(x2)	53.3	20	5	11.1
Sta. 388+20 MAXWELL RD.	38	30	126.7	38	5	21.1
Sta. 405+35 NORWOOD BLVD.	30	12(x2)	80	30	5	16.7
Sta. 417+59 SILVER MAPLE LN.	23	12	30.7	23	5	12.8
Sta. 4XX+XX RAINBOW DR.	20	12	26.7	20	5	11.1
Sta. 458+XX N. CHRIST CHURCH RD.	22	12	29.3	22	5	12.2
Sta. 458+XX S. STONE CHURCH RD.	22	12	29.3	22	5	12.2
Sta. 497+20 SUPER CHEVY DR.	15					
Sta. 506+27.5 CEMETERY SERVICE RD.	25	12	33.3	25	5	13.9
TOTALS	793		1467	793		441

INCIDENTAL HOT-MIX ASPHALT SURFACING, 2 1/4"				
LOCATION	40800050			
	Width	Length	SQYD	TON
Sta. 270+64.70 N. KICKAPOO CRK. RD.	25	18	50	6.3
Sta. 270+55.31 S. KICKAPOO CRK. RD.	25	18	50	6.3
Sta. 272+08 E. REDBUD DR.	20	12	26.7	3.36
Sta. 302+18 N. HILLTOP RD.	20	12	26.7	3.36
Sta. 306+40 OAKLEAF RD.	22	12	29.3	3.7
Sta. 311+14 SUNSET DR.	20	12	26.7	3.36
Sta. 317+48 W. REDBUD DR.	28	18	56	7
Sta. 317+48 FERNWOOD CIRCLE	28	12	37.3	4.7
Sta. 322+23 LIMESTONE LN.	28	12	37.3	4.7
Sta. 332+20 ANDERSON LN.	22	12	29.3	3.7
Sta. 334+13 -336+83 BRIDGE OMISSION				
Sta. 338+29 HIGHLAND DR.	15	12	20	2.5
Sta. 340+47 TRADEWIND DR.	30	12	40	5
Sta. 341+74 COUNTRY LN.	22	12	29.3	3.7
Sta. 343+90 TOWER RD.	26	18	52	6.55
Sta. 348+32 TIMBERLAKE LN.	22	12	29.3	3.7
Sta. 351+30 RANGE RD.	20	12	26.7	3.36
Sta. 356+95 SHELTON LN.	18	12	24	3
Sta. 367+95 DEMPSTER LN.	20	12	26.7	3.36
Sta. 373+70 FARM. RD. STORAGE	20	12	26.7	3.36
Sta. 376+72 WILDWOOD CT.	20	12	26.7	3.36
Sta. 380+07 CHERRY ST.	20	12	26.7	3.36
Sta. 383+18 WOODS RD.	20	12(x2)	53.3	6.7
Sta. 388+20 MAXWELL RD.	38	30	126.7	16
Sta. 405+35 NORWOOD BLVD.	30	12(x2)	80	10
Sta. 417+59 SILVER MAPLE LN.	23	12	30.7	3.87
Sta. 4XX+XX RAINBOW DR.	20	12	26.7	3.36
Sta. 458+XX N. CHRIST CHURCH RD.	22	12	29.3	3.7
Sta. 458+XX S. STONE CHURCH RD.	22	12	29.3	3.7
Sta. 497+20 SUPER CHEVY DR.	15			
Sta. 506+27.5 CEMETERY SERVICE RD.	25	12	33.3	4.2
Sta. 508+76.79 EOP IL.116/PLANK RD.				
SUB-TOTAL			1107	139.4
HMA PRIVATE ENTRANCES (44)			195.5	24.6
TOTAL			1302	164.1

CONVERSION: 112 LBS./SQYD/2.25" = TONS

PRIME COAT CONVERSION FACTORS		
SURFACE TYPE	BIT PR COAT	AGG PR COAT
	(GAL/SQ YD)	(LB/SQ YD)
COLD MILLED SURFACES	0.1	4
EXISTING PAVEMENT	0.05	4
NEW BITUMINOUS COURSES	0.03	2

BITUMINOUS & AGGREGATE CONVERSION FACTORS	
SURFACE TYPE	
BIT. SURF. COURSES	112 LB /SQ YD/IN
ALL OTHER BIT.	112 LB /SQ YD/IN
AGGREGATE SHOULDERS	2.05 TONS/CUYD

TRAFFIC CONTROL SCHEDULE					
LOCATION	70100450	70101205	70100460	70100500	70100600
	T,C, & P. STD.	T,C, & P. STD.	T,C, & P. STD.	T,C, & P. STD.	T,C, & P. STD.
	701201 (LSUM)	701321 SPECIAL (EACH)	701306 (LSUM)	701326 (LSUM)	701336 (LSUM)
STA. 333+83 TO STA. 337+13	1	1			
ENTIRE PROJECT			1	1	1
TOTALS	1	1	1	1	1

S:\GEN\DRIFT\STDB\PLANS\SUB\414P-Contract\68502 Farmington Rd.dgn

FILE NAME = 68502 Farmington Rd.dgn

USER NAME = jonesce	DESIGNED - CEJ	REVISED - ---
PLOT SCALE = 103.7851' / IN.	DRAWN - CEJ	REVISED - ---
PLOT DATE = 1/25/2010	CHECKED - ENE	REVISED - ---
	DATE - 01/15/2010	REVISED - ---

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES		
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.

F.A.U. RTE. 6659	SECTION 11RS-3	COUNTY PEORIA	TOTAL SHEETS 40	SHEET NO. 11
PPP			CONTRACT NO. 68502	
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

FARMINGTON RD. 3P-from KICKAPOO CRK. to IL.116