

| SHORT-TERM PAVEMENT MARKING | | |
|-----------------------------|----------------|------------------|
| LOCATION | LENGTH FOOT | 70300100 FOOT |
| ENTIRE PROJECT | 23853 | 7163 |
| TOTAL | | 7163 |

| RAISED REFLECTIVE PAVEMENT MARKERS | |
|------------------------------------|------------------|
| LOCATION | 78100100 EACH |
| MAINLINE | 330 |
| MAXWELL RD. | 18 |
| TOTAL | 348 |

| RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL | |
|--|------------------|
| LOCATION | 78300200 EACH |
| MAINLINE | 330 |
| MAXWELL RD. | 18 |
| TOTAL | 348 |

| STRUCTURE PAY ITEMS SCHEDULE | | | | |
|------------------------------|---------------------|----------------------------|-------------------------------------|-----------------|
| LOCATION | CONCRETE REMOVAL | CONCRETE SUPERSTRUCTURE | REINFORCEMENT BARS, EPOXY COATED | BAR SPLICERS |
| | 50102400 | 50300255 | 50800205 | 50800515 |
| | CU YD | CU YD | POUND | EACH |
| STA. 334+13 TO STA. 336+83 | | | | 16 |
| TOTALS | | | | 16 |

| STRUCTURE PAY ITEMS SCHEDULE (CONTIN.) | | | | | | | | | | |
|--|-------------------------------|-------------------------------------|----------------------------|-----------------------------------|--------------------------------|----------------------------|---------------------------------|------------------------|--------------------------------|---------------------------------|
| LOCATION | PREFORMED JOINT STRIP SEAL | TEMPORARY BRIDGE TRAFFIC SIGNALS | CHANGEABLE MESSAGE SIGN | PVMT. MRKG. TAPE, TYPE III, 4" | WORKZONE PVMT. MARKING REM. | TEMPORARY CONC. BARRIER | RELOCATE TEMP. CONC. BARRIER | Pvmt. Mrkg. Removal | IMPACT ATTEN. TEMP. NRD TL3 | IMPACT ATTEN. RELOC. NRD TL3 |
| | 52000110 | 70106500 | 70106800 | 70300520 | 70301000 | 70400100 | 70400200 | 78300105 | Z0030250 | Z0030350 |
| | FOOT | EACH | CAL MO | FOOT | SQ FT | FOOT | FOOT | FOOT | EACH | EACH |
| STA. 334+13 TO STA. 336+83 | 98 | 1 | 2 | 1968 | 656 | 375 | 362 | 1256 | 2 | 2 |
| TOTALS | 98 | 1 | 2 | 1968 | 656 | 375 | 362 | 1256 | 2 | 2 |

| TEMPORARY PAVEMENT MARKING - LINE 4" | | | | | | |
|--------------------------------------|-----------------|---------------------------|--------------|---------------------|-----------------------|--------------|
| EPOXY PAVEMENT MARKING - LINE 4" | | | | | | |
| LOCATION | LENGTH (Ft.) | EOP(x2) WHITE SOLID | Q YELLOW | | | |
| | | | Lt. SOLID | Q(x2) DBL. YELL. | Q(x 1/3) SKIP DASH | Rt. SOLID |
| Sta. 270+64 - Sta. 301+74 | 3110 | 3110 | | 3150 | | |
| Sta. 301+74 - Sta. 306+24 | 450 | 450 | | | 300 | 300 |
| Sta. 306+74 - Sta. 326+24 | 1950 | 1950 | 450 | | 450 | |
| Sta. 326+74 - Sta. 384+20 | 5746 | 5746 | | | 5746 | |
| Sta. 384+20 - Sta. 388+20 | 400 | 400 | | 1960 | 400 | 400 |
| MAXWELL RD. INTERSECTION | | | | 110 | | |
| Sta. 388+20 - Sta. 395+55 | 735 | 735 | 735 | | 735 | |
| Sta. 395+55 - Sta. 414+20 | 1865 | 1865 | | | 1865 | 1865 |
| Sta. 414+20 - Sta. 425+20 | 1100 | 1100 | 1100 | | 1100 | |
| Sta. 425+20 - Sta. 437+50 | 1230 | 1230 | | | 1230 | |
| Sta. 437+50 - Sta. 482+00 | 4450 | 4450 | | | 4450 | |
| Sta. 482+00 - Sta. 507+00 | 2500 | 2500 | | 2500 | | |
| FARMINGTON RD./RT.116 JUNCT. | | | | | | |
| Sta. 507+00 - Sta. 508+77 | 177 | 177 | | 177 | | |
| SUB-TOTAL | | 47626 | 2285 | 15794 | 4883 | 2565 |
| INTERSECTIONS | 740 | | | | | |
| SIDE RD. DEDUCTION | | 1350 | | | | |
| TOTAL | | | | 72543 | | |

| INTERSECTION EPOXY PAVEMENT MARKING SCHEDULE | | | | | | | |
|--|-----------------|------------------------------|-------------|-------------|--------------|--------------|--------------------------------|
| LOCATION | LENGTH (Ft.) | INTERSECTION PAINTED MEDIANS | | | | | Letters & Symb. (Sq.Ft.) |
| | | 4' WHITE | 6' WHITE | 8" WHITE | 12" WHITE | 24" WHITE | |
| KICKAPOO CREEK RD. | | | | | | 24 | |
| FARMINGTON RD./MAXWELL RD. | | | | | | | |
| Sta. 388+13.5 - Sta. 389+26.5 | 213 | 190 | 140 | 498 | 285 | 36 | 93.6 |
| FARMINGTON RD. / RT.116 | | | | | | | |
| Sta. 507+00 - Sta. 508+77 | 177 | 550 | | 415 | 170 | 26 | 31.2 |
| TOTALS | | 740 | 140 | 913 | 455 | 86 | 172 |