

SCHEDULE OF SIDE ROADS AND ENTRANCES

LOCATION	AREA SQ YD	POLYMERIZED BIT. MATERIALS (PRIME COAT)	AGGREGATE PRIME COAT	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	INCIDENTAL HMA SURFACING	HMA SURFACE REMOVAL, 3/4 IN	HMA SURFACE REMOVAL, 1 1/2 IN	HMA SURFACE REMOVAL, 2 IN	AGGREGATE SURFACE CSE TYPE B	
		TON	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD	SQ YD	TON	
SIDE ROADS:											
LT./RT. STA. 397+04.20 CALLENDAR ST.	438.89	0.23	1.32	55.56	27.78	55.30			438.89		
LT./RT. STA. 400+30.42 ALLEY	130.00	0.07	0.39	40.00	20.00	16.38			130.00		
RT. STA. 403+59.12 ALLEY	57.00	0.03	0.17	15.56	7.78	7.18			57.00		
LT./RT. STA. 405+22.47 MAJOR ST.	339.33	0.18	1.02	87.78	43.89	42.76			339.33		
LT./RT. STA. 409+27.80 DARST ST.							NO WORK				
LT. STA. 411+03.00 ALLEY	158.33	0.08	0.48	39.81	19.91	19.95			158.33		
LT./RT. STA. 412+78.00 CREAMERY ST.	316.66	0.16	0.95	79.62	39.81	39.90			316.66		
RT. STA. 419+63.00 HENRY ST.	158.33	0.08	0.48	39.81	19.91	19.95			158.33		
RT. STA. 423+65.00 KELLER ST.	158.33	0.08	0.48	39.81	19.91	19.95			158.33		
LT. STA. 436+00.00 ± E. BULLOCK ST.	158.33	0.08	0.48	39.81	19.91	19.95			158.33		
RT. STA. 436+00.00 ± EAST ST.	158.33	0.08	0.48	39.81	19.91	19.95			158.33		
LT./RT. STA. 531+44.00 1625 E	332.70	0.17	1.00	104.40	52.20	41.92	332.70				
LT./RT. STA. 571+04.00 1700 E	323.30	0.17	0.97	115.60	57.80	40.74	323.30				
LT. STA. 625+42.00 1800 E	190.00	0.10	0.57	62.20	31.10	23.94	190.00				
RT. STA. 651+82.00 1850 E	198.30	0.10	0.59	53.30	26.65	24.99	198.30				
LT./RT. STA. 678+22.00 1900 E	346.60	0.18	1.04	97.80	48.90	43.67	346.60				
LT./RT. STA. 731+02.00 2000 E	296.00	0.15	0.89	142.30	71.15	37.30	296.00				
LT./RT. STA. 2427+60.00 2100 E	693.30	0.36	2.08	55.56	27.78	87.36	693.30				
LT./RT. STA. 2454+00.00 2150 E	1,152.50	0.60	3.46	55.56	27.78	145.22	1,152.50				
RT. STA. 2506+81.00 2250 E	180.56	0.09	0.54	27.78	13.89	22.75	180.56				
LT. STA. 2546+24.00 2325 E	88.89	0.05	0.27	22.22	11.11	11.20	88.89				
LT. STA. 2589+00.00 2425 E	122.22	0.06	0.37	24.44	12.22	15.40	122.22				
RT. STA. 2638+70.00 2500 E	73.33	0.04	0.22	24.44	12.22	9.24	73.33				
LT./RT. STA. 2691+60.00 2600 E	133.33	0.07	0.40	44.44	22.22	16.80	133.33				
LT./RT. STA. 104+50.00 ACESS RD.	280.00	0.15	0.84	55.56	27.78	23.52		280.00			
RT. STA. 749+48.00 MICHIGAN ST.	95.00	0.05	0.29	27.78	13.89	7.98		95.00			
LT./RT. STA. 753+20.00 SUMMIT ST.	200.00	0.10	0.60	55.56	27.78	16.80		200.00			
LT./RT. STA. 757+00.00 WALNUT ST.	210.00	0.11	0.63	55.56	27.78	17.64		210.00			
LT./RT. STA. 760+79.00 SYCAMORE ST.	190.00	0.10	0.57	55.56	27.78	15.96		190.00			
LT./RT. STA. 764+60.00 ELM ST.	190.00	0.10	0.57	55.56	27.78	15.96		190.00			
RT. STA. 768+42.00 S. CENTRAL ST.	110.00	0.06	0.33	27.78	13.89	9.24		110.00			
RT. STA. 774+63.00 COMMERCIAL ST.	40.00	0.02	0.12	27.78	13.89	3.36		40.00			
LT. STA. 779+29.00 CHESTNUT ST.	110.00	0.06	0.33	27.78	13.89	9.24		110.00			
LT. STA. 783+14.00 PINE ST.	120.00	0.06	0.36	27.78	13.89	10.08		120.00			
RT. STA. 786+85.00 MAPLE ST.	210.00	0.11	0.63	27.78	13.89	17.64		210.00			
RT. STA. 790+65.00 ORANGE ST.	105.00	0.05	0.32	27.78	13.89	8.82		105.00			
LT./RT. STA. 798+20.00 OAK ST.	220.00	0.11	0.66	55.56	27.78	18.48		220.00			

FILE NAME = 68570 - Phase II.dgn

USER NAME = johnsonv	DESIGNED -	REVISED -
PLOT SCALE = 100.0000 / IN.	DRAWN -	REVISED -
PLOT DATE = 2/1/2010	CHECKED -	REVISED -
	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 2 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	31RS-2+30,39RS-3+32,33RS-4	WOODFORD	41	15
CONTRACT NO. 68570				
ILLINOIS FED. AID PROJECT				