

**SCHEDULE OF SIDE ROADS AND ENTRANCES**

LOCATION	AREA SQ YD	POLYMERIZED BIT. MATERIALS (PRIME COAT)	AGGREGATE PRIME COAT	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	INCIDENTAL HMA SURFACING	HMA SURFACE REMOVAL, 3/4 IN	HMA SURFACE REMOVAL, 1 1/2 IN	HMA SURFACE REMOVAL, 2 IN	AGGREGATE SURFACE CSE TYPE B	
		TON	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD	SQ YD	TON	
<b>ENTRANCES AND MAILBOX TURNOUTS</b>											
RT. STA. 791+49.00	CE	124.00	0.06	0.37		10.42		124.00			
LT. STA. 791+66.00	CE	124.00	0.06	0.37		10.42		124.00			
RT. STA. 792+10.00	CE	124.00	0.06	0.37		10.42		124.00			
LT. STA. 796+22.00	CE	124.00	0.06	0.37		10.42		124.00			
LT. STA. 797+65.00	CE	124.00	0.06	0.37		10.42		124.00			
LT. STA. 799+50.00	PE & MB	40.89	0.02	0.12		3.43		40.89			
LT. STA. 801+50.00	PE & MB	40.89	0.02	0.12		3.43		40.89			
RT. STA. 804+16.00	PE	78.00	0.04	0.23		6.55		78.00			
LT. STA. 804+30.00	PE & MB	40.89	0.02	0.12		3.43		40.89			
LT. STA. 811+24.00	CE	124.00	0.06	0.37		10.42		124.00			
LT. STA. 811+96.00	CE	124.00	0.06	0.37		10.42		124.00			
LT. STA. 814+55.00	CE	124.00	0.06	0.37		10.42		124.00			
RT. STA. 825+24.00	PE	78.00	0.04	0.23		6.55		78.00			
RT. STA. 826+65.00	PE	78.00	0.04	0.23		6.55		78.00			
LT. STA. 830+00.00	CE	124.00	0.06	0.37		10.42		124.00			
LT. STA. 831+00.00	PE	78.00	0.04	0.23		6.55		78.00			
LT. STA. 833+29.00	CE	124.00	0.06	0.37		10.42		124.00			
LT. STA. 834+80.00	CE	124.00	0.06	0.37		10.42		124.00			
<b>SUBTOTAL</b>			5.93	34.20	1,835.38	917.69	1,263.16	5,200.42	4,126.67	2,073.55	207.94
<b>TOTAL</b>			<b>6</b>	<b>34</b>	<b>1,835</b>	<b>918</b>	<b>1,263</b>	<b>5,200</b>	<b>4,127</b>	<b>2,074</b>	<b>208</b>

**PRIME COAT CONVERSION FACTORS**

SURFACE TYPE	BIT PR COAT	AGG PR COAT
	(GAL/SQ YD)	(LB/SQ YD)
COLD MILLED SURFACES	0.1	4
EXISTING PAVEMENT	0.05	4
NEW HMA COURSES	0.03	2

**HMA & AGGREGATE CONVERSION FACTORS**

SURFACE TYPE	LB	TON
	SQ YD IN	CU YD
HMA COURSES	112	2.016
COARSE AGGREGATE	114	2.05
FINE AGGREGATE		1.5

**MATERIAL TRANSFER DEVICE**

LOCATION	TON
US 24 - HMA SURFACE COURSE ONLY	18,264
<b>TOTAL</b>	<b>18,264</b>