

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	100% STATE SAFETY-2A FULTON COUNTY		
		UNIT	TOTAL	RURAL
20200500	EARTH EXCAVATION (WIDENING)	CUYD	156	156
28001000	AGGREGATE (EROSION CONTROL)	TON	72.2	72.2
35650400	BASE COURSE WIDENING, 9"	SQYD	623	623
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GAL	78	78
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQYD	599	599
40600990	TEMPORARY RAMP	SQYD	115	115
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	59	59
42001300	PROTECTIVE COAT	SQYD	445	445
44000700	APPROACH SLAB REMOVAL	SQYD	9	9
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQYD	430	430
50102400	CONCRETE REMOVAL	CUYD	14.8	14.8
50300255	CONCRETE SUPERSTRUCTURE	CUYD	20.4	20.4
50300260	BRIDGE DECK GROOVING	SQYD	430	430
50400105	PRECAST CONCRETE BRIDGE SLAB	SOFT	600	600
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2720	2720
50800515	BAR SPLICERS	EACH	24	24
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	80	80
52000110	PREFORMED JOINT STRIP SEAL	FOOT	106	106
67100100	MOBILIZATION	LSUM	1	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	LSUM	1	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1
70106700	TEMPORARY RUMBLE STRIP	EACH	12	12

CODE NO.	ITEM	100% STATE SAFETY-2A FULTON COUNTY		
		UNIT	TOTAL	RURAL
70106800	CHANGEABLE MESSAGE SIGN	CALMO	2	2
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	1952	1952
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SOFT	651	651
70400100	TEMPORARY CONCRETE BARRIER	FOOT	325	325
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	250	250
* 78005110	EPOXY MARKING - LINE 4"	FOOT	1250	1250
78300105	PAVEMENT MARKING REMOVAL	FOOT	1250	1250
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQYD	410	410
X0324744	REMOVAL OF EXISTING PRECAST CONCRETE UNITS	SOFT	600	600
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SOFT	148	148
X7200201	WIDTH RESTRICTION SIGNING	LSUM	1	1
Z0012200	BRIDGE DECK HYDRO-SCARIFICATION (1/2 INCH)	SQYD	430	430
Z0016000	DECK SLAB REPAIR (FULL DEPTH)	SOYD	25	25
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
X0321460	PLUG EXISTING DECK DRAINS	EACH	7	7

\* SPECIALTY ITEM

SN.029-0027 IL.  
97 over BigCrk.

FILE NAME = SN.029-0027 IL.97 over BigCrk.dgn	USER NAME = jonesce	DESIGNED - CEJ	REVISED - ---	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE. 622	SECTION (128BR-11)	COUNTY FULTON	TOTAL SHEETS 23	SHEET NO. 3	
	PLOT SCALE = 103.7851' / IN.	DRAWN - CEJ	REVISED - ---				MISC. BRIDGE REPAIRS				CONTRACT NO. 68927
	PLOT DATE = 2/5/2010	CHECKED - ---	REVISED - ---			SCALE: _____					
		DATE - -----	REVISED - ---			SHEET NO. ___ OF ___ SHEETS					STA. _____ TO STA. _____

S:\GEN. DRAFT. STD&PLNS\SDA0414\ BRIDGE CONTRACTS\JOINTS\ 68927\ SN.029-0027 IL.97 over BigCrk.dgn