

RAISED REFLECTIVE PAVEMENT MARKERS	
LOCATION STATION TO STATION	78100100 EACH
STA 461+07 TO STA 469+36	10
STA 469+36 TO STA 477+12	19
STA 477+12 TO STA 479+55.9	6
STA 479+55.9 TO STA 488+33	11
STA 488+33 TO STA 492+37	10
STA 492+37 TO STA 509+09	21
STA 509+09 TO STA 515+44	16
STA 515+44 TO STA 532+70.55	22
STA 532+70.55 TO STA 545+05.45	31
STA 545+05.45 TO STA 556+19	14
STA EQ 556+19 = 50+93	
STA 50+93 TO STA 248+23.71	247
STA 248+23.71 TO STA 258+36.29	25
STA 258+36.29 TO STA 281+07.33	28
STA 281+07.33 TO STA 289+87.77	22
STA 289+87.77 TO STA 582+45	366
TOTAL	848

SHOULDER RUMBLE STRIPS		
LOCATION STATION TO STATION	LENGTH FOOT	64200105 FOOT
LT&RT STA 193+90 TO STA 339+86	29,192.0	29,192.0
TOTAL		29,192

AGGREGATE SHOULDER, TYPE B		
LOCATION STATION TO STATION	LENGTH FOOT	48101200 TON
LT&RT STA 461+07 TO STA 556+19	9,512.00	586
STA EQ 556+19 = 50+93		
LT&RT STA 50+93 TO STA 513+40	46,247.00	2851
TOTAL		3,438

CLASS D PATCHES, 14 INCH			
LOCATION FROM TO	44201815 TYPE II (SQ YD)	44201819 TYPE III (SQ YD)	44201821 TYPE IV (SQ YD)
120' N OF IL116/IL89 TO MADISON ST	49	23	87
MADISON ST TO 1500N RD	468	17	144
1500N RD TO 1600N RD	272	237	1,676
1600N RD TO 1675N RD	358	173	316
1675N RD TO BLACK PARTRIDGE ST	352	156	0
BLACK PARTRIDGE TO MAIN ST(CAZENOVIA)	347	35	0
MAIN ST(CAZENOVIA) TO BANTA RD	439	104	173
BANTA RD TO CLARK ST	312	173	269
CLARK ST TO 2100N RD	696	104	0
2100N RD TO 2200N RD	416	116	213
2200N RD TO END OF PROJECT	497	0	40
TOTAL	4,206	1,138	2,918

STRIP REFLECTIVE CRACK CONTROL	
LOCATION STATION TO STATION	44300200 FT
STA 461+07 TO STA 477+12	1,605
STA 477+12 TO STA 556+19	7,907
STA EQ 556+19 = 50+93	
STA 50+93 TO STA 528+45	47,752
SUB-TOTAL	57,264
TOTAL (Entire Project)	85,896

RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL	
LOCATION STATION TO STATION	78300200 EACH
ENTIRE PROJECT	670
TOTAL	670

MOBILIZATION	
LOCATION	67100100 L SUM
ENTIRE PROJECT	1
TOTAL	1

CONSTRUCTING TEST STRIP	
LOCATION	40600895 EACH
ENTIRE PROJECT	1
TOTAL	1

HOT-MIX ASPHALT SHOULDER, 8"			
LOCATION STATION TO STATION	WIDTH FT	AREA SQ FT	48203029 SQ YD
STA EQ 556+19 = 50+93			
LT&RT STA 193+90 TO STA 202+88	5	8,980.00	997.78
LT STA 202+88 TO STA 203+93	5	525	58.33
TOTAL			1,056

TRAFFIC CONTROL SCHEDULE			
LOCATION	70100500 TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	70100460 TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	70100600 TRAFFIC CONTROL AND PROTECTION, STANDARD 701336
	L SUM	L SUM	L SUM
ENTIRE PROJECT	1	1	1
TOTALS	1	1	1

MOWING	
LOCATION	X2503100 UNIT
ENTIRE PROJECT	568
TOTAL	568