

SCHEDULES OF QUANTITIES

78000200 THERMOPLASTIC PAVEMENT MARKING, LINE 4"

STA.	TO	STA.	4" WHITE (FEET)	4" YELLOW (FEET)	TOTAL (FEET)
2270+54.60		2298+12.86	1,878.0	5,952.0	7,830.0
2298+14.21		2303+23.32	347.0	1,098.0	1,445.0
2305+13.70		2362+39.04	3,941.0	12,233.0	16,174.0
100+00.00		105+64.00	384.0	1,217.0	1,601.0
GRAND TOTAL =					27,050.0

78000600 THERMOPLASTIC PAVEMENT MARKING, LINE 12"

STA.	TO	STA.	# DIAGONALS	AVE. LENGTH (FEET)	TOTAL LENGTH (FEET)
2288+38		2294+95	23	9'	207.0
2296+17		2298+59	11	8'	88.0
TOTAL =					295.0
ROUND TO:					300.0

78000650 THERMOPLASTIC PAVEMENT MARKING, LINE 24"

STA.	TO	STA.	OFFSET	LENGTH (FEET)
TANNER STREET				
2294+94		2294+94	RT.	50.0
2295+00		2295+50	LT.	50.0
2296+18		2296+18	LT.	50.0
2295+48		2295+98	RT.	50.0
FREDRICK STREET				
2313+33		2313+35	RT.	34.0
2314+18		2314+20	LT.	37.0
GROVE STREET				
2348+44		2348+46	RT.	37.0
2349+43		2349+45	LT.	50.0
MAPLEWOOD DRIVE				
100+02		100+05	RT.	45.0
101+11		101+13	LT.	47.0
STOP BARS TOTAL =				450.0

78000400 THERMOPLASTIC PAVEMENT MARKING, LINE 6"

STREET	STA.	TO	STA.	LENGTH (FEET)
TANNER MAINLINE	2295+00 RT.		2295+00 LT.	111.0
TANNER MAINLINE	2295+06 RT.		2296+06 LT.	107.0
TANNER MAINLINE	2296+07 RT.		2296+07 LT.	107.0
TANNER MAINLINE	2296+13 RT.		2296+13 LT.	109.0
TANNER	2294+97 LT.		2296+04 LT.	107.0
TANNER	2294+99 LT.		2296+01 LT.	102.0
TANNER	2295+07 RT.		2296+09 RT.	102.0
TANNER	2295+07 RT.		2296+09 RT.	102.0
GERRARD MAINLINE	2299+52 LT.		2299+55 RT.	80.0
GERRARD MAINLINE	2299+58 LT.		2299+61 RT.	83.0
GERRARD MAINLINE	2300+22 RT.		2300+24 LT.	79.0
GERRARD MAINLINE	2300+28 RT.		2300+30 LT.	76.0
GERRARD	649+56 LT.		649+58 RT.	60.0
GERRARD	649+62 LT.		649+64 RT.	61.0
GERRARD	650+42 RT.		650+45 LT.	66.0
GERRARD	650+48 RT.		650+51 LT.	67.0
FREDRICK	2313+39 RT.		2313+39 LT.	58.0
FREDRICK	2313+45 RT.		2313+45 LT.	61.0
FREDRICK	2314+08 RT.		2314+08 LT.	74.0
FREDRICK	2314+14 RT.		2314+14 LT.	65.0
CHANUTE	2330+29 RT.		2330+53 LT.	62.0
CHANUTE	2330+35 RT.		2330+59 LT.	83.0
GROVE	2349+33 RT.		2349+33 LT.	80.0
GROVE	2349+39 RT.		2349+39 LT.	78.0
MAPLEWOOD	100+08 RT.		100+11 LT.	81.0
MAPLEWOOD	100+14 RT.		100+17 LT.	88.0
MAPLEWOOD	101+01 RT.		101+01 LT.	89.0
MAPLEWOOD	101+07 RT.		101+07 LT.	87.0
CROSSWALK TOTAL =				2,325.0

TRAFFIC SIGNAL PAY ITEMS

STREET	CONDUIT IN TRENCH, 1" DIA., PVC 81012300 (FOOT)	CONDUIT IN TRENCH, 1 1/2" DIA., PVC 81012500 (FOOT)	HANDHOLE 81400100 (EACH)	TRENCH AND BACKFILL FOR ELECTRICAL WORK 81900200 (FOOT)	DETECTOR LOOP, TYPE 1 88600100 (FOOT)
TANNER	0.0	0.0	0.0	0.0	139.0
FREDRICK	20.0	4.0	2.0	24.0	128.0
GROVE	0.0	0.0	0.0	0.0	368.0
MAPLEWOOD	0.0	0.0	0.0	0.0	373.0
TOTALS =	20.0	4.0	2.0	24.0	1008.0